STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
EXIT 12 RAMP D STA. 10+87.35 RT	EAST VERMONT 117	1	24	12	2.00						2												2	X 13/14.25= 207.1LBS								X	M3-2		E-136B
		1	30	24	5.00																													M6-1		E-136B
		1	21	15	2.19																															E-136B
	TO INTERSTATE 89	1	24	12	2.00																													M4-5		E-135
		1	24	24	4.00																													MI-1		E-135
		1	21	15	2.19																													M6-1		E-135
	WEST VERMONT 117	1	24	12	2.00																													M3-4		E-136B
		1	30	24	5.00																															E-136B
		1	21	15	2.19																													M6-2R		E-136B
EXIT 12 RAMP D STA. 13+16.59 RT		1	18	18	2.25						1			X 8		X																	OMI-1		E-150
EXIT 12 RAMP D STA. 13+42.30 LT	DO NOT ENTER ONE WAY ONE WAY	1	30	30	6.25						1			X 14		X																	R5-1		E-143
		1	36	12	3.00																													R6-1R BACK TO BACK		E-142
		1	36	12	3.00																													R6-1L		E-142
EXIT 12 RAMP D STA. 13+42.30 RT	DO NOT ENTER ONE WAY ONE WAY	1	30	30	6.25						1			X 14		X																	R5-1		E-143
		1	36	12	3.00																													R6-1R BACK TO BACK		E-142
		1	36	12	3.00																													R6-1L		E-142
EXIT 12 RAMP D STA. 13+31.25 RT	DO NOT ENTER	1	30	30	6.25						2			X 14/14		X																	R5-1 BACK TO BACK		E-143
		1	36	36	3.75 ~~4.50~~																													R1-2		E-146
	ONE WAY ONE WAY	1	36	12	3.00																													R6-1L BACK TO BACK		E-142
		1	36	12	3.00																													R6-1R		E-142
EXIT 12 RAMP B STA. 14+47.07 LT		1	30	36	7.50						1			X 14		X																	WI-8		E-150
EXIT 12 RAMP B STA. 15+02.67 LT		1	30	36	7.50						1			X				1															WI-8 SLEEVE REQUIRED - FLANGED CHANNEL SIGN POST FOR THIS ASSEMBLY IS MODIFIED TO INCLUDED THE COST OF THE SLEEVE.		E-150
EXIT 12 RAMP B STA. 14+91.32 RT	DO NOT ENTER	1	30	30	6.25						1			X 14		X																	R5-1 BACK TO BACK		E-143
		1	30	30	6.25																													R3-2		E-143
EXIT 12 RAMP B STA. 4+52.13 RT	PROHIBITED REGULATIONS STOPPING FOR WORKERS ANNUALS FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 16/16		X																	VR-046		E-142
EXIT 12 RAMP B STA. 3+11.26 RT		1	36	36	3.75 ~~4.50~~						2			X 16/16		X																	RI-2		E-146
EXIT 12 RAMP B STA. 1+92.30 LT	1170 0406 0240	1	6	10	0.42						1	X 8			X																					E-143
EXIT 12 RAMP B STA. 1+79.65 LT		1	18	18	2.25						1			X 8		X																	OMI-1		E-150
												FT 8.00	FT	FT 180.00	FT 8.00	FT	FT 180.00		EA	LB	LB	LB		LB 228	LB	LB	LB								

FT 15.00 (MOD.)

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TOTALS	SF	SF	EA.	SF		FT	FT	LB	EA.	LB	EA.	EA.	LB
	113.74					172.00 ~~188.00~~ 15.00 (MOD.)	188.00		2	~~228~~ 207.1			

TRAFFIC SIGN SUMMARY SHEET 14

PROJECT NAME: ESSEX
PROJECT NUMBER: NH 2403 (I)S

FILE NAME: pave/04b032/p04b032.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p04b032ssl4.I

PLOT DATE: 23-APR-2009 15:5
DRAWN BY: SJB, RHB
CHECKED BY: EPD
SHEET 37 OF 48