STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAMMER REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																									
	SHEET 24 TOTAL				162.79							16.0		315.0	16.0	315.0							2	228.0													
	SHEET 25 TOTAL				99.68	30.00	2					8.0		300.0	8.0	300.0							2	228.0													
	SHEET 26 TOTAL				64.26	228.00						24.0	16.0	120.0	40.0	120.0							4	354.0				2		777						
	SHEET 27 TOTAL				81.06	253.00						32.0	16.0	90.0	48.0	90.0												4		1531						
	SHEET 28 TOTAL				61.76	170.00						24.0		195.0	24.0	195.0							2	228.0												
	SHEET 29 TOTAL				113.26									255.0		255.0																				
	SHEET 30 TOTAL				96.13	30.00								255.0		255.0							2	228.0												
	SHEET 31 TOTAL				74.51	137.50						24.0		75.0	24.0	75.0																				
	SHEET 32 TOTAL				85.25	128.00							16.0	270.0	16.0	270.0							2	228.0												
	SHEET 33 TOTAL				119.50	30.00							15.0	(MOD.) 330.0		330.0							2	228.0												
	SHEET 34 TOTAL				105.56	162.50						32.0		150.0	32.0	150.0							2	167.0				4		889.5						
	SHEET 35 TOTAL				114.01	102.00						24.0	16.0	240.0	40.0	240.0							2	213.0				2		517.5						
	SHEET 36 TOTAL				136.89	107.00						16.0		225.0	16.0	225.0							2	228.0				2		420						
													90.0	(MOD.)																						
	SHEET 37 TOTAL				113.74							8.0		180.0	8.0	180.0							2	228.0												
													15.0	(MOD.)																						
	SHEET TOTALS				1428.4	1378.0	2					208.0	64.0	3000.0	272.0	3000.0							24	2558.0				14		4135						
													120.0	(MOD.)																						
	ROUNDING				71.6	22.0	-					42.0	36.0	30.0	78.0	30.0							-	42.0				-		65						
	PROJECT TOTALS				1500.0	1400.0	2					250.0	100.0	3030.0	350.0	3030.0							24	2600.0				14		4200						
													120.0	(MOD.)																						
												FT 250	FT 100	FT 3030	FT 350	FT 3030	FT		EA	LB	LB	LB		LB	LB	LB	LB									
					SF	SF	EA.	SF				FT 3380 120.0 (MOD.)			FT 3380					LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 15

PROJECT NAME: ESSEX
PROJECT NUMBER: NH 2403 (I)S

FILE NAME: pave/04b032/p04b032.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p04b032ssl5.i

PLOT DATE: 23-APR-2009 15:5
DRAWN BY: SJB, RHB
CHECKED BY: EPD
SHEET 38 OF 48