



**ASPHALTIC PLUG-TYPE  
JOINT DETAIL  
REMOVAL OF >2"  
DETERIORATED CONCRETE**

NOTES:

1. UPON ENCOUNTERING GREATER THAN 2" AVERAGE OF DETERIORATED CONCRETE, THE CONTRACTOR SHALL REMOVE THE DETERIORATED MATERIAL AND REPLACE IT WITH RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE.
2. REMOVAL OF THE DETERIORATED CONCRETE WILL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 580.20 "RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE".
3. THE STEEL PLATE IN THE ASPHALTIC PLUG JOINT MAY BE OMITTED ONLY IF THE REPAIRED SURFACE IS SO IRREGULAR IT WILL CAUSE VERTICAL MOVEMENT AND IT IS DIRECTED BY THE RESIDENT ENGINEER.

**PROJECT  
TYPICAL  
SHEET 4**

PROJECT NAME: SPRINGFIELD  
PROJECT NUMBER: STP 2405(1)S

FILE NAME: /pave/04b038/pb038.dgn  
PROJECT LEADER: M. WOOLAVER  
DESIGNED BY: JLR  
pb038+y04.i

PLOT DATE: 19-JUN-2012 08:16  
DRAWN BY: JLR  
CHECKED BY: JLR  
SHEET 6 OF 42