QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL C.E.	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			-	-	-	2	2	EA	THINNING AND TRIMMING	201.31	-
			-	-	-	25	25	CY	COMMON EXCAVATION	203.15	EST.
			-	-	-	405	405	CY	EARTH BORROW	203.30	3
			-	-	-	1	1	CY	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	-
			-	-	-	158,600	158,600	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	68
			-	-	-	49,500	49,500	LF	MILLED RUMBLE STRIPS	213.10	427
			-	-	-	50	50	TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	EST.
			-	-	-	1250	1250	TON	AGGREGATE SHOULDERS (MOD.)	402.12	6
			-	-	-	400	400	CWT	EMULSIFIED ASPHALT	404.65	5
			-	-	-	1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
			-	-	-	22,300	22,300	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	143
			-	-	90	-	90	LF	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG)	516.10	2
			-	-	100	-	100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL W/ COARSE AGGREGATE	580.20	EST.
			-	-	-	51	51	EA	REHABING DI, CB OR MH, CLASS I	604.412	-
			-	-	-	100	100	HR	POWER GRADER RENTAL	608.15	EST.
			-	-	-	100	100	HR	ALL PURPOSE EXCAVATOR RENTAL TYPE I	608.25	EST.
			-	-	-	100	100	HR	POWER BROOM RENTAL	608.30	EST.
			-	-	-	25	25	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
			-	-	-	150	150	HR	TRUCK RENTAL	608.37	EST.
			-	-	-	10	10	MGAL	DUST CONTROL WITH WATER	609.10	EST.
			-	-	-	35	35	CY	STONE FILL, TYPE I	613.10	3
			-	-	-	2432	2432	LF	TREATED TIMBER CURB	616.35	-
			-	-	-	10	10	LF	REMOVING AND RESETTING CURB	616.40	EST.
			-	-	-	10	10	LF	REMOVAL OF EXISTING CURB	616.41	EST.
			-	-	-	125	125	EA	YIELDING MARKER POSTS	619.17	EST.
			-	-	-	12,225	12,225	LF	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	-
			-	-	-	1512.5	1512.5	LF	STEEL BEAM GUARDRAIL (GALVANIZED) (MOD. - 8' POSTS)	621.20	-
			-	-	-	19	19	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
			-	-	-	19	19	EA	TRAILING END TERMINAL	621.52	-
			-	-	-	163.8	163.8	LF	ALUMINUM APPROACH RAILING	621.74	-
			-	-	-	13,575	13,575	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
			-	-	-	1400	1400	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			-	-	-	2100	2100	HR	FLAGGERS	630.15	EST.
			1	-	-	-	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
			1	-	-	-	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
			1	-	-	-	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BITUMINOUS PAVEMENT
155,918	SY	MAINLINE
1058	SY	SIDE ROADS
1556	SY	PARKING AREA
68	SY	ROUNDING
158,600	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)
4343	TON	LEVELING COURSE (TYPE IVS)
17,369	TON	WEARING COURSE (TYPE IIIS)
107	TON	WEARING COURSE (TYPE IVS)
119	TON	SIDE ROADS
219	TON	PARKING AREA
143	TON	ROUNDING
22,300	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #1

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: NH 2408(I)S

FILE NAME: p04b050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p04b050qsl.i

PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 6 OF 80