

ITEM DETAIL SUMMARY SHEET 2

LOCATION			GUARDRAIL							MISCELLANEOUS				REMARKS	
BEGIN STATION	END STATION	POS.	621.20	621.20	621.505	621.505	621.52	621.60	621.74	621.80	604.412	616.35	616.40		616.41
			STEEL BEAM GUARDRAIL (GALVANIZED) LF	SB GR (GALV.) (MOD. W/8' POSTS) LF	MANUF. TERMINAL SECTION EA	MANUF. TERM. SECT. (FLARED) EA	TRAILING END TERMINAL EA	ANCHOR FOR S.B. RAIL EA	ALUMINUM APPROACH RAILING LF	REMOVAL & DISPOSAL GUARDRAIL LF	REHABING DI, CB, MH CLASS I EA	TREATED TIMBER CURB LF	REMOVING & RESETTING CURB LF		REMOVAL OF EXISTING CURB LF
CLARENDON:															
121+70.0	126+84.0	LT	462.5							490		464			INSTALL NEW TRAILING END TERMINAL FROM STA. 121+70.0 TO STA. 121+84.0. INSTALL NEW TREATED TIMBER CURB FROM STA. 121+75.0 TO STA. 124+31.0 AND FROM STA. 124+35.0 TO STA. 126+43.0. INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) FROM STA. 126+46.5 TO STA. 126+84.0.
121+81.0		LT													
123+32.0	126+46.0	RT	262.5							176					INSTALL NEW TRAILING END TERMINAL FROM STA. 123+32.0 TO STA. 123+46.0. INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) FROM STA. 126+08.5 TO STA. 126+46.0.
129+83.0		RT													
131+29.0		LT													
134+22.0		LT													
134+22.0		RT													
152+71.0		RT													
176+94.0	180+81.5	RT	350							180					CONNECT TO EXISTING GUARDRAIL AT STA. 176+94.0. INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) FROM STA. 180+44.0 TO STA. 180+81.5.
176+94.0	179+70.5	LT	225							175					INSTALL NEW TRAILING END TERMINAL FROM STA. 176+94.0 TO STA. 177+08.0. INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) FROM STA. 179+33.0 TO STA. 179+70.5.
176+98.0		RT													
179+53.0		RT													
186+39.0		RT													
190+33.0		RT													
194+36.0		RT													
198+33.0		LT													
198+33.0		RT													
202+37.0		LT													
202+37.0		RT													
205+88.0		LT													
205+88.0		RT													
208+27.0	213+78.5	LT	500							539		400			INSTALL NEW TRAILING END TERMINAL FROM STA. 208+27.0 TO STA. 208+41.0. INSTALL TREATED TIMBER CURB FROM STA. 208+65.0 TO STA. 212+65.0. INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) FROM STA. 213+41.0 TO STA. 213+78.5.
209+38.0		RT													
210+95.0		LT													
217+35.0		RT													
219+19.0	229+08.0	LT	937.5							975					INSTALL NEW TRAILING END TERMINAL FROM STA. 219+19.0 TO STA. 219+33.0. INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) FROM STA. 228+70.5 TO STA. 229+08.0.
241+33.0	244+97.0	LT	312.5							353					INSTALL NEW TRAILING END TERMINAL FROM STA. 241+33.0 TO STA. 241+47.0. INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) FROM STA. 244+59.5 TO STA. 244+97.0.
SHEET SUBTOTAL			3050			7	6			2888	20	864			

ITEM DETAIL SUMMARY SHEET #2	PROJECT NAME: WALLINGFORD - RUTLAND TOWN	
	PROJECT NUMBER: NH 2408(1)S	
	FILE NAME: p04b050.dgn	PLOT DATE: \$DATE\$
PROJECT LEADER: D.E.G.	DRAWN BY: C.A.K.	
DESIGNED BY: J.S.P.	CHECKED BY: D.E.G.	
IPARM FILE: p04b050ids2.1	SHEET 10 OF 80	