STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
														OPTION ITEMS ( )																							
CLARENDON: 72+87.0, LT	MILL RIVER	1	36	24	6.00						~~2~~ 1			13' X																					E-131
	BRIDGE 90-S US 7	1	6	8	0.33																												SIGN ID CODE VD-701		E-134
74+05.0, LT	SPEED LIMIT 55	1	36	48	12.00						2			16'-6" X 17'																			SIGN ID CODE R2-1		E-142
	EMERGENCY STOPPING ONLY	1	30	24	5.00																												SIGN ID CODE R8-7		E-142
74+87.0, LT	0070 1105 0140	1	6	10	0.42						1	9' X			X			X																		
76+05.0, LT	SOUTH	1	30	15	3.13						2			15' X 16'																			SIGN ID CODE M3-3		E-136A
	7	1	36	36	9.00																												SIGN ID CODE MI-4		E-136A
77+20.0, LT	MIDDLE RD MIDDLE RD						1 1				1			12'-6" X		X		X															SALVAGED SIGNS TO BE MOUNTED ON NEW POST. BACK-TO-BACK	- -	- -
77+27.0, LT	ONE WAY ONE WAY	1 1	36 36	12 12	3.00 3.00						2			14' X 14'																			BACK-TO-BACK SIGN ID CODE R6-1R SIGN ID CODE R6-1L		E-142 E-142
	STOP 0070 1105 0147	1 1	30 6	30 10	6.25 0.42																												SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
	DIVIDED HIGHWAY	1	24	18	3.00																												SIGN ID CODE R6-3	65	
												LF - (14)	LF	LF 112 (14)	LF - (14)	LF - (14)	LF		EA	LB	LB	LB		LB	LB	LB	LB								
														127																						
TOTALS		SF 51.55	SF	EA. 2	SF							LF 112 (28)			LF - (28)					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: NH 2408(I)S

FILE NAME: p04b050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p04b050tss06.i
PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 46 OF 80