STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS ( )																								
CLARENDON: 80+75.0, LT	ONLY ONLY / WRONG WAY	1 1	60 36	30 24	12.50 6.00						2			15' X 15'-8"																			BACK-TO-BACK SIGN ID CODE VR-941 SIGN ID CODE R5-1A		E-145B E-143
80+75.0, RT	ONLY ONLY / WRONG WAY	1 1	60 36	30 24	12.50 6.00						2			15'-1" X 15'-8"																			BACK-TO-BACK SIGN ID CODE VR-941 SIGN ID CODE R5-1A		E-145B E-143
82+75.0, LT	BRIDGE ICES BEFORE ROAD	1	48	48	16.00						2			16'-4" X 16'-11"																			SIGN ID CODE W8-13		E-150
84+75.0, LT	JCT	1	21	15	2.19						2			15' X 16'																			SIGN ID CODE M2-1		E-136B
	VERMONT 7B	1	36	36	9.00																												SIGN ID CODE MI-5		E-136B
85+43.0, LT	0070 1105 0160	1	6	10	0.42						1	9' X			X			X															SIGN ID CODE VD-700		E-138
88+00.0, LT	7A NORTH NEXT LEFT / Clarendon NEXT RIGHT	1	138	126		120.75					2																	20'-6" 2 24'-3"		805.5 ~~812~~	W8x18		CALCULATED INDIVIDUAL BOLT TENSION IS 18.4 KIPS	65	
												LF - (14)	LF	LF 112 (-)	LF - (14)	LF	LF		EA	LB	LB	LB		LB	LB	LB	LB								
														134.67																						
TOTALS			SF 64.61	SF 120.75	EA.	SF						LF 112 (14)			LF - (14)					LB			EA.	LB				EA. 2	EA.	LB ~~812~~ 805.5					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: NH 2408(1)S

FILE NAME: p04b050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p04b050tss08.i
PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 48 OF 80