STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS ( )																							
CLARENDON: 182+70.0, LT	SOUTH SOUTH	1 1	30 30	15 15	3.13 3.13						2											2	218.5 ~~262~~	14'-11" 13'-10"							X	SIGN ID CODE M3-3 SIGN ID CODE M3-3		E-136B E-136A
	VERMONT 103 7	1 1	45 36	36 36	11.25 9.00																											SIGN ID CODE M1-5 SIGN ID CODE M1-4		E-136B E-136A
	← ↑	1 1	21 21	15 15	2.19 2.19																											SIGN ID CODE M6-1 SIGN ID CODE M6-3		E-136B E-136A
185+00.0, LT	JCT	1	21	15	2.19						2			15'-2" X 15'-9"																		SIGN ID CODE M2-1		E-136B
	VERMONT 103	1	45	36	11.25																											SIGN ID CODE M1-5		E-136B
189+47 LT		1	24	24	4.00																														
189+47.0, LT	103 SOUTH Ludlow NEXT LEFT	1	138	108		103.50					2											2				655.69 ~~657~~	23'-1" 21'-10"							65	
189+55.0, LT	0070 1105 0360	1	6	10	0.42						1	9' X			X			X														SIGN ID CODE VD-700		E-138
195+61.0, LT	Rutland Airport NEXT LEFT	1	108	84		63.00					2											2			374.44 ~~402~~	17'-6" 17'-2"							63	
200+11.0, LT	0070 1105 0380	1	6	10	0.42						1	8' X			X			X														SIGN ID CODE VD-700		E-138
201+75.0, LT	JUNCTION 103 1/2 MILE	1	102	102		72.25					2											2			385.13 ~~412~~	18'-4" 17'-4"							63	
210+67.0, LT	0070 1105 0400	1	6	10	0.42						1	8' X			X			X														SIGN ID CODE VD-700		E-138
												LF - (42)	LF	LF 28 (-)	LF - (42)	LF	LF		EA	LB	LB	LB		LB 218.5 ~~262~~	LB	LB 759.57 ~~814~~	LB 655.69 ~~657~~								
												55.92																							
TOTALS			SF 45.59	SF 238.75	EA.	SF						LF 28 (42)			LF - (42)					LB		EA. 8	LB 1633.76 ~~1733~~				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: NH 2408(1)S

FILE NAME: p04b050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p04b050tss13.i
PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 53 OF 80