STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 18

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS ( )																							
CLARENDON: 286+88.0, LT	N Shrewsbury NEXT LEFT / N Clarendon NEXT RIGHT	1	168	120		140.00					2															21'-6" 24'-3"	2		960.75 ~~1057~~	W8x21		CALCULATED INDIVIDUAL BOLT TENSION IS 20.1 KIPS	67	
286+88 LT		1 1	24 24	24 6	4.00 1.00																														
289+55.0, LT		1	12	36	3.00						1			10'-6" X		X		X															SIGN ID CODE OM-3R		E-120
290+00.0, LT	COLD RIVER	1	36	24	6.00						1 ~~2~~			13'-6" X																					E-131
	BRIDGE 96-S US 7	1	6	8	0.33																												SIGN ID CODE VD-701		E-134
290+71.0, LT	SOUTH	1	30	15	3.13						2			16' X 15'-6"																			SIGN ID CODE M3-3		E-136A
	7	1	36	36	9.00																												SIGN ID CODE MI-4		E-136A
292+61.0, LT	Wallingford 8 / Manchester 30 / Bennington 52	1	144	78		78.00					2												2			498.88 ~~501~~								66	
293+18.0, LT	ONE WAY / ONE WAY	1 1	36 36	12 12	3.00 3.00						2			14' X 14'																			BACK-TO-BACK SIGN ID CODE R6-1R SIGN ID CODE R6-1L		E-142 E-142
	STOP / 0070 1105 0556	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
	DIVIDED HIGHWAY	1	24	18	3.00																												SIGN ID CODE R6-3	65	
					42.13							LF	LF	LF 84 (14) 83.5	LF	LF - (14)	LF		EA	LB	LB	LB		LB	LB	LB	LB 498.88 ~~501~~								
TOTALS					SF ~~37.13~~	SF 218.00	EA.	SF				LF 84 (14)			LF - (14)					LB			EA. 2	LB 498.88 ~~501~~				EA. 2	EA.	LB 960.75 ~~1057~~					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: NH 2408(1)S

FILE NAME: p04b050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p04b050tss18.i
PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 58 OF 80