STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 20

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS ( )																									
RUTLAND TOWN: 7+52.0, LT		1	18	18	2.25						1	9' X			X			X																SIGN ID CODE OMI-1		E-150
10+00.0, LT	ONLY ONLY	1	60	30	12.50						2			14' X 15'-8																				SIGN ID CODE VR-941		E-145A
10+50.0, LT	0070 1120 0020	1	6	10	0.42						1	9' X			X			X																SIGN ID CODE VD-700		E-138
11+41.0, LT	Middle Road	1	120	48		40.00																												SIGN SHALL BE MOUNTED OVER EXISTING OVERHEAD SIGN PANEL TO COMPLETELY COVER "RIGHT TURN/ U-TURN" TEXT. CONTRACTOR SHALL FIELD VERIFY ACTUAL SIGN DIMENSIONS PRIOR TO FABRICATION.	66	
		1	120	36		30.00	ADDED PER R.E., T.P.																											DID NOT RETAIN EXISTING OVERHEAD SIGN PANEL.		
16+71.0, RT	ONE WAY	1	36	12	3.00						2			11'-6" X 11'-6"																				SIGN ID CODE R6-1L		E-142
18+49.0, LT		1	36	36	9.00						2			13' X 13'-8"																				SIGN ID CODE W4-1		E-150
21+00.0, LT	0070 1120 0040	1	6	10	0.42						1	8' X			X			X																SIGN ID CODE VD-700		E-138
21+75.0, LT	ONLY	1	48	30	10.00						2			14' X 14'-6"																				SIGN ID CODE VR-935		E-145B
						70.00						LF - (42)	LF	LF 112 (-) 133.84	LF - (42)	LF	LF		EA	LB	LB	LB		LB	LB	LB	LB									
TOTALS		SF 37.59	SF ~~40.00~~	EA.	SF							LF 112 (42)			LF - (42)					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: NH 2408(I)S

FILE NAME: p04b050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: p04b050tss20.1
PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 60 OF 80