

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							520				520		CY	COMMON EXCAVATION	203.15				
									210		210		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							130				130		CY	SAND BORROW	203.31				
							10	10			20		CY	TRENCH EXCAVATION OF EARTH	204.20				
									900		900		CY	STRUCTURE EXCAVATION	204.25				
									500		500		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
							315				315		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
							170				170		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
							3				3		CWT	EMULSIFIED ASPHALT	404.65				
							250				250		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.27				
									80		80		SY	SHEET MEMBRANE WATERPROFNG, PREFORMED SHEET	519.21				
									1		1		EACH	REMOVAL OF STRUCTURE (975 SF - EST.)	529.15				
									1		1		LS	PRECAST CONCRETE STRUCTURE (15' X 9' X 80' BOX)	540.10				
							10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
							8				8		CY	STONE FILL, TYPE I	613.10				
									12		12		CY	STONE FILL, TYPE II	613.11				
									200		200		CY	STONE FILL, TYPE III	613.12				
							450				450		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215				
							3				3		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50				
							434				434		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							100				100		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							410				410		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402				
							410				410		LF	DURABLE 4 INCH YELLOW LNE, THERMOPLASTIC	646.412				
									275		275		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								10			10		LB	SEED	651.15				
								60			60		LB	FERTILIZER	651.18				
							.5				.5		TON	AGRICULTURAL LIMESTONE	651.20				
							.5				.5		TON	HAYMULCH	651.25				
							70				70		SY	GRUBBING MATERIAL	651.40				
							1				1		LS	EPSC PLAN	652.10				
							15				15		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							620				620		SY	TEMPORARY EROSION MATTING	653.20				

PROJECT NAME: JAY
 PROJECT NUMBER: ST STP CULV(2)
 FILE NAME: S04B140QS.XLS
 PROJECT MANAGER: W. SYMONDS
 DESIGNED BY: T. FILLBACH
 QUANTITY SHEET #1
 PLOT DATE: 10/10/2006
 DRAWN BY: G. SHANGRAW
 CHECKED BY: J. LACROIX
 SHEET 5 OF 39