STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STATION MP 1.02 RT VT 110	JCT M2-1, JUNCTION	1	21	15	2.19						1			X		X		1																INSTALL NEW SIGN ON NEW POST		STD. E-136A
	302 MI-4, US ROUTE MARKER	1	30	24	5.00																												INSTALL NEW SIGN ON NEW POST, (SUB-MOUNT W/ PREVIOUS SIGN)		STD. E-136A
STATION MP 1.02 RT VT 110	END M4-6	1	24	12	2.00						1			X		X		1																INSTALL NEW SIGN ON NEW POST		STD. E-140
	VERMONT 110 STATE ROUTE MARKER	1	30	24	5.00																												INSTALL NEW SIGN ON NEW POST, (SUB-MOUNT W/ PREVIOUS SIGN)		STD. E-136B
STATION 52+40, LT VT 110	R4-7, KEEP RIGHT	1	24	30	5.00						1			X	X			1	1														INSTALL NEW SIGN ON NEW POST		STD. E-144
	OMI-1	1	18	18	2.25																												INSTALL NEW SIGN ON NEW POST, (SUB-MOUNT W/ PREVIOUS SIGN)		STD. E-150
STATION 52+42, RT VT 110	STOP RI-1, STOP SIGN	1	30	30	6.25						1			X	X			1															◯	INSTALL NEW SIGN ON NEW POST		STD. E-143
STATION 52+45, RT VT 110	W11-2, PEDESTRIAN CROSSING	1	30	30	6.25						1			X		X		1																INSTALL NEW SIGN ON NEW POST TYPE IX RETROREFLECTIVE SHEETING WITH FLUORESCENT YELLOW-GREEN BACKGROUND		STD. 152
	W16-7p, ARROW DOWN LT	1	24	12	2.00																												INSTALL NEW SIGN ON NEW POST, (SUB-MOUNT W/ PREVIOUS SIGN) TYPE IX RETROREFLECTIVE SHEETING WITH FLUORESCENT YELLOW-GREEN BACKGROUND		STD. 152
STATION 52+75, LT VT 110	W11-2, PEDESTRIAN CROSSING	1	30	30	6.25						1			X		X		1																INSTALL NEW SIGN ON NEW POST TYPE IX RETROREFLECTIVE SHEETING WITH FLUORESCENT YELLOW-GREEN BACKGROUND		STD. 152
	W16-7p, ARROW DOWN LT	1	24	12	2.00																												INSTALL NEW SIGN ON NEW POSTS, (SUB-MOUNT W/ PREVIOUS SIGN) TYPE IX RETROREFLECTIVE SHEETING WITH FLUORESCENT YELLOW-GREEN BACKGROUND		STD. 152
STATION 53+01, LT VT 110	SOUTH M3-3, CARDINAL DIRECTION MARKER	1	24	12	2.00						1			X		X		1	1														INSTALL NEW SIGN ON NEW POST		STD. E-136B
	VERMONT 110 STATE ROUTE MARKER	1	30	24	5.00																												INSTALL NEW SIGN ON NEW POST (SUB-MOUNT W/ PREVIOUS SIGN)		STD. E-136B
	M6-2R DIRECTION ARROW	1	21	15	2.19																												INSTALL NEW SIGN ON NEW POSTS, (SUB-MOUNT W/ PREVIOUS SIGNS)		STD. E-136B
STATION 53+04, RT VT 110	YIELD RI-2, YIELD	1	36	36	4.50						1			X	X			1	1														INSTALL NEW SIGN ON NEW POST		STD. E-146
STATION 53+17, RT VT 110	YIELD RI-2, YIELD	1	36	36	4.50						1			X	X			1															INSTALL NEW SIGN ON NEW POST		STD. E-146
												LF	LF	LF	LF	LF	LF		EA	LB	LB	LB		LB	LB	LB	LB								
														117.00	61.00	74.00			3																	
TOTALS		SF 62.38	SF	EA.	SF							LF 117.00			LF 135.00					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BARRE TOWN
PROJECT NUMBER: HES 026-I(38)

FILE NAME: z04b198tss.dgn
PROJECT LEADER: JOSHUA SCHULTZ
DESIGNED BY: E. ATKINS/W.WONG
TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 1/30/2008
DRAWN BY: WING WONG
CHECKED BY: KO ISHIKURA