

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								325			325		CY	COMMON EXCAVATION	203.15				
								1275			1275		SY	COLD PLANING-BIT.PAVEMENT	210.10				
								700			700		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
								25			25		TON	AGGREGATE SHOULDERS	402.12				
								7			7		CWT	EMULSIFIED ASPHALT	404.65				
								1185			1185		TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25				
								20			20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
								5			5		HR	POWER BROOM RENTAL	608.30				
								10			10		HR	TRUCK RENTAL	608.37				
								80			80		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								80			80		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE-ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17				
										1	1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25				
								1			1		LS	MOBILIZATION / DEMOBILIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL	641.10				
								2350			2350		LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40				
								2500			2500		LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41				
								210			210		LF	DURABLE 8" YELLOW LINE (THERMOPLASTIC)	646.43				
								135			135		LF	DURABLE 24" STOP BAR (THERMOPLASTIC)	646.46				
								12			12		EACH	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50				
								2350			2350		LF	TEMPORARY 4" WHITE LINE (PAINT)	646.60				
								2950			2950		LF	TEMPORARY 4" WHITE LINE (TAPE, TYPE II)	646.60				
								2500			2500		LF	TEMPORARY 4" YELLOW LINE (PAINT)	646.61				
								2900			2900		LF	TEMPORARY 4" YELLOW LINE (TAPE, TYPE II)	646.61				
								135			135		LF	TEMPORARY 24" STOP BAR (PAINT)	646.66				
								12			12		EACH	TEMPORARY LETTERS OR SYMBOLS (PAINT)	646.70				
								570			570		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
								25			25		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								30			30		LB	SEED	651.15				
								120			120		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAYMULCH	651.25				
								10			10		CY	TOPSOIL	651.35				
								1			1		LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10				
								5			5		HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20				
								1			1		LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30				
								13			13		SF	TRAFFIC SIGNS, TYPE A	675.20				
								18			18		LF	FLANGED CHANNEL SIGN POST	675.301				
								1			1		EACH	REMOVING SIGNS	675.50				

PROJECT NAME: **SWANTON**
PROJECT NUMBER: **HES 036-1(12)**
FILE NAME: 04b212con.xls PLOT DATE: 09/18/2006
PROJECT MANAGER: NYQUIST DRAWN BY: JFG/SHE
DESIGNED BY: JFG CHECKED BY: traffic
QUANTITY SHEET #1 SHEET 3 OF 16