COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

HUBBARDTON ST 0161(23)		CASTLETON-SUDBURY STP 2402(I)S			SUMMARY OF ESTIMATED QUANTITIES				
EROSION CONTROL	ROADWAY	FULL C.E.	EMPLOYEE TRAINEESHIP	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
-	1	-	-	-	1	LS	CLEARING AND GRUBBING (INCL. INDV. TREES & STUMPS)	201.10	
-	20	-	-	200	220	CY	COMMON EXCAVATION	203.15	
-	-	-	-	10	10	CY	EARTH BORROW	203.30	
-	3510	-	-	-	3510	SY	FINE GRADING - SUBGRADE	203.40	
-	-	-	-	1	1	CY	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	
-	3210	-	-	4700	7910	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	
-	940	-	-	400	1340	TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	
-	3210	-	-	-	3210	SY	RECLAIMED STABILIZED BASE	310.20	
-	-	-	-	3300	3300	TON	AGGREGATE SHOULDERS	402.12	
-	350	-	-	160	510	TON	AGGREGATE SHOULDERS (MOD.)	402.12	
-	10	-	-	510	520	CWT	EMULSIFIED ASPHALT	404.65	
-	1070	-	-	28,500	29570	TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.27	
-	-	-	-	1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
-	-	-	-	4	4	EA	REHABING DI, CB OR MH, CLASS I	604.412	
-	-	-	-	200	200	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	
-	-	-	-	100	100	HR	POWER BROOM RENTAL	608.30	
-	-	-	-	300	300	HR	TRUCK RENTAL	608.37	
-	170	-	-	-	170	MGAL	DUST CONTROL WITH WATER	609.10	
-	-	-	-	1000	1000	CY	STONE FILL, TYPE I	613.10	
-	-	-	-	170	170	EA	YIELDING MARKER POSTS	619.17	
2430	-	-	-	-	2430	LF	SNOW FENCE (MOD. - PDF)	620.70	
2280	-	-	-	-	2280	LF	MISCELLANEOUS FENCE (MOD. - SEDIMENT LOG)	620.80	
-	-	-	-	2450	2450	LF	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	
-	-	-	-	3100	3100	LF	STEEL BEAM GUARDRAIL (GALVANIZED) (MOD. - 8' POSTS)	621.20	
-	1694	-	-	-	1694	LF	BOX BEAM GUARDRAIL (MOD. - 7' POSTS & 3' POST SPACING)	621.30	
-	-	-	-	30	30	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	
-	4	-	-	-	4	EA	MANUFACTURED TERMINAL SECTION (MOD.)	621.505	
-	-	-	-	2	2	EA	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505	
-	-	-	-	15	15	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
-	1465	-	-	4700	6165	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	
-	-	-	-	10	10	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	
-	150	-	-	1500	1650	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
-	150	-	-	2000	2150	HR	FLAGGERS	630.15	
-	-	1	-	-	1	LS	FIELD OFFICE - ENGINEERS	631.10	
-	-	1	-	-	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
-	-	1	-	-	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
-	-	1	-	-	1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	
-	-	-	1040	-	1040	HR	EMPLOYEE TRAINEESHIP	634.10	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

PROJECT NAME: CASTLETON-SUDBURY/HUBBARDTON
PROJECT NUMBER: STP 2402(I)S / ST 0161(23)

FILE NAME: 03c044-04c028.dgn
PROJECT LEADER:
DESIGNED BY:
IPARM FILE: 03c044-04c028qsl.i

PLOT DATE: 27-MAR-2006
DRAWN BY: J.A.D
CHECKED BY: T.B.G.
SHEET 2 OF 92