STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 / 1.88	SQUARE STEEL (in) lb/ft 2.0 / 2.16	SQUARE STEEL (in) lb/ft 2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 / 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 / 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD / 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 / 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 / 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 / 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REFRAMED SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
CASTLETON: 292+30.0, LT	STOP 0300 1103 0554	1 1	30 6	30 10	6.25 0.42						1			X		X		X															BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
339+23.0, LT	FLOAT BRIDGE RD						1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0300 1103 0643	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
339+56.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X															SIGN ID CODE VR-017		E-141
HUBBARDTON: 47+18.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X															SIGN ID CODE VR-017		E-141
	SPEED LIMIT 35						1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
47+77.0, RT	PENCIL MILL RD						1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0300 1108 0091	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
67+61.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X															SIGN ID CODE VR-017		E-141
	SPEED LIMIT 35						1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST.		
												LF	LF	LF 84.0	LF	LF 84.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 37.26	SF	EA. 4	SF				LF 84.0			LF 84.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: CASTLETON - SUDBURY
PROJECT NUMBER: STP 2402(I)S

FILE NAME: p04c028.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p04c028tss2.i

PLOT DATE: 11-JUN-2007 13:34
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 41 OF 92