

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1		1		LS	CLEARING AND GRUBBING (INCL. INDV. TREES & STUMPS)	201.10				
								20		20		CY	COMMON EXCAVATION	203.15	5			
								3510		3510		SY	FINE GRADING-SUBGRADE	203.40	37			
								3210		3210		SY	COLD PLANING-BIT.PAVEMENT	210.10	30			
								940		940		TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	12			
								3210		3210		SY	RECLAIMED STABILIZED BASE	310.20	30			
								350		350		TON	AGGREGATE SHOULDERS (MOD.)	402.12	4			
								10		10		CWT	EMULSIFIED ASPHALT	404.65	1			
								1070		1070		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.27	10			
								170		170		MGAL	DUST CONTROL WITH WATER	609.10	2			
									2430	2430		LF	SNOW FENCE (MOD. - PDF)	620.70	24			
									2280	2280		LF	MISCELLANEOUS FENCE (MOD. - SEDIMENT LOG)	620.80	27			
								1694		1694		LF	BOX BEAM GUARD RAIL (MOD. - 7' POSTS & 3' POST SPACING)	621.30				
								4		4		EACH	MANUFACTURED TERMINAL SECTION (MOD.)	621.505				
								1466		1466		LF	REMOVL AND DISP OF GUARD RAIL	621.80				
								150		150		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								150		150		HR	FLAGGERS	630.15				
								.1		.1		LS	MOBILIZATION / DEMOBILIZATION	635.11				
								.1		.1		LS	TRAFFIC CONTROL	641.10				
								2525		2525		LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40	25			
								2525		2525		LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41	25			
								5050		5050		LF	TEMPORARY 4" WHITE LINE (PAINT)	646.60	50			
								5050		5050		LF	TEMPORARY 4" YELLOW LINE (PAINT)	646.61	50			
								1250		1250		EACH	LINE STRIPING TARGETS	646.76				
								11		11		LB	SEED	651.15	1			
								90		90		LB	FERTILIZER	651.18	4			
								1		1		TON	AGRICULTURAL LIMESTONE	651.20	.6			
								1		1		TON	HAY MULCH	651.25	.6			
								50		50		CY	TOPSOIL	651.35	4			
								1		1		LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10				
								60		60		HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20				
								1		1		LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30				
								7		7		SF	TRAFFIC SIGNS, TYPE A	675.20				
								16		16		LF	FLANGED CHANNEL SIGN POST	675.301				
								18		18		LF	FLANGED CHANNEL SIGN POST (BEGIN SIGN POST OPTION ITEMS)	675.301				
								18		18		LF	SQUARE TUBE SIGN POSTS AND ANCHOR (END SIGN POST OPTION ITEMS)	675.341				
								3		3		EACH	REMOVING SIGNS	675.50				

PROJECT NAME: HUBBARDTON  
 PROJECT NUMBER: ST 0161(23)  
 FILE NAME: 03c044/DESIGN/d03c044frm  
 PROJECT MANAGER: K. UPMAL  
 DESIGNED BY: J. DEVLIN  
 QUANTITY SHEET  
 PLOT DATE: 02/27/2006  
 DRAWN BY: J. DEVLIN  
 CHECKED BY: R. DELLASANTA  
 SHEET 60 OF 92