

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				Roadway	Erosion Control	Bridge	Full C&E	Alternate ZA	Alternate ZB		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				4							4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
				4							4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED NETC 2 RAIL	621.72				
				400							400		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
				40							40		LF	TEMPORARY TRAFFIC BARRIER	621.90				
				150							150		HR	FLAGGERS	630.15				
							1				1		LS	FIELD OFFICE, ENGINEERS	631.10				
							1				1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
							1				1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
							1				1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
				1							1		LS	MOBILIZATION/DEMobilIZATION	635.11				
				1540							1540		LF	4 INCH WHITE LINE	646.20				
				1540							1540		LF	4 INCH YELLOW LINE	646.21				
						840					840		SY	GEOTEXTILE UNDER STONE FILL	649.31				
					245						245		SY	GEOTEXTILE FOR SILT FENCE	649.51				
					120						120		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
					130						130		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
					50						50		LB	SEED	651.15				
					200						200		LB	FERTILIZER	651.18				
					2						2		TON	AGRICULTURAL LIMESTONE	651.20				
					3						3		TON	HAYMULCH	651.25				
				105							105		CY	TOPSOIL	651.35				
						400					400		SY	GRUBBING MATERIAL	651.40				
					1						1		LS	EPSC PLAN	652.10				
					150						150		HR	MONITORING EPSC PLAN	652.20				
					1						1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
					1000						1000		SY	TEMPORARY EROSION MATTING	653.20				
					16						16		CY	VEHICLE TRACKING PAD	653.35				
					748						748		LF	BARRIER FENCE	653.50				
					752						752		LF	PROJECT DEMARICATION FENCE	653.55				
				1							1		SF	TRAFFIC SIGNS, TYPE A	675.20				
				16							16		LF	FLANGED CHANNEL SIGN POST	675.301				
				4							4		EACH	DELINEATOR WITH STEEL POST	676.10				
						150					150		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT) (FPQ)	900.608				
						1360					1360		CY	SPECIAL PROVISION (LIGHTWEIGHT BACKFILL)	900.608				
				1							1		LS	SPECIAL PROVISION (DRYHYDRANT)	900.645				
				1							1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
				1							1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
						420					420		SY	SPECIAL PROVISION (LONGITUDINAL DECK GROOVING)	900.675				
				840							840		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				