

# QUANTITY SHEET #1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES							
										BRIDGE	EROSION CONTROL	ROADWAY	FULL C&E ITEMS	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
												1				1		LS	CLEARING AND GRUBBING (INCL. INDV. TREES & STUMPS)	201.10			
												1013			7	1020		CY	COMMON EXCAVATION	203.15			
												32			8	40		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27			
												1154			6	1160		CY	STRUCTURE EXCAVATION	204.25			
												967			3	970		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30			
												340				340		SY	COLD PLANING-BIT PAVEMENT	210.10			
												760				760		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35			
												5			5	5		CWT	EMULSIFIED ASPHALT	404.65			
												417			8	425		TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25			
										1446					4	1450		SF	TEMPORARY STEEL SHEET PILING	505.36			
										4					4	4		GAL	WATER REPELLENT (MOD. -SILANE)	514.10			
										60					60	60		SY	SHEET MEMBRANE WATERPROOFING (PREFORMED SHEET)	519.20			
												1			1	1		LS	ONE-WAY TEMPORARY BRIDGE (7' X 25' CGMP) (MOD)	528.10			
										1					1	1		EACH	REMOVAL OF STRUCTURE (7' X 56' CGMPP)	529.15			
										1					1	1		LS	PRECAST CONCRETE STRUCTURE (15' X 8' X 56' BOX)	540.10			
												5			5	5		HR	BULLDOZER RENTAL, TYPE I	608.10			
												5			5	5		HR	POWER GRADER RENTAL	608.15			
												50			50	50		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25			
												5			5	5		HR	TRUCK RENTAL	608.37			
												5			5	5		HR	LOADER RENTAL, TYPE I	608.40			
												34			34	34		CY	STONE FILL, TYPE I	613.10			
												40			40	40		CY	STONE FILL, TYPE II	613.11			
										107					107	107		CY	STONE FILL, TYPE II (MOD)	613.11			
										1					1	1		LS	TEMPORARY RELOCATION OF STREAM	614.10			
											650				650	650		LF	SNOW FENCE (MOD - PDF)	620.70			
												342			342	342		LF	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20			
												4			4	4		EACH	MANUFACTURED TERMINAL SECTION (FLARED)	621.505			
												415			415	415		LF	REMOVL AND DISP OF GUARD RAIL	621.80			
												750			750	750		LF	TEMPORARY TRAFFIC BARRIER	621.90			
												40			40	40		HR	UNIFORMED TRAFFIC OFFICERS	630.10			
												40			40	40		HR	FLAGGERS	630.15			
													1		1	1		LS	FIELD OFFICE-ENGINEERS	631.10			
													1		1	1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17			
														1	1	1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25			
												1			1	1		LS	MOBILIZATION / DEMOBILIZATION	635.11			
												1			1	1		LS	TRAFFIC CONTROL	641.10			
												700			700	700		LF	4" WHITE LINE	646.20			
												700			700	700		LF	4" YELLOW LINE	646.21			
												25			25	25		EACH	LINE STRIPING TARGETS	646.76			
												200			200	200		SY	GEOTEXTILE UNDER STONE FILL	649.31			

PROJECT NAME: **BUELS GORE**  
PROJECT NUMBER: **STP ST CULV(1)**  
FILE NAME: 04c138/str/s04c138qs.dgn PLOT DATE: 25-APR-2006  
PROJECT MANAGER: M.EVANS-MONGEON DRAWN BY: W.FARLEY  
DESIGNED BY: W.FARLEY CHECKED BY: M.EVANS-MONGEON  
QUANTITY SHEET #1 SHEET 4 OF 30