

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES											TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	CHANNEL	SUPER-STRUCTURE	ABUT. #1	ABUT. #2	EROSION CONTROL	FULL CE ITEMS	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS			
1									1		LS	MOBILIZATION/DEMobilIZATION	635.11						
1									1		LS	TRAFFIC CONTROL	641.10						
1200									1200		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402						
1100									1100		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412						
25									25		LF	DURABLE 24 INCH STOP BAR	646.480						
4									4		EA	DURABLE LETTER OR SYMBOL	646.490						
100									100		EACH	LINE STRIPING TARGETS	646.76						
	560								560		SY	GEOTEXTILE UNDER STONE FILL	649.31						
					110				110		SY	GEOTEXTILE FOR SILT FENCE	649.51						
					20				20		LB	SEED	651.15						
					10				10		LB	SEED, WINTER RYE	651.17						
					100				100		LB	FERTILIZER	651.18						
					1				1		T	AGRICULTURAL LIMESTONE	651.20						
					1				1		T	HAY MULCH	651.25						
					70				70		CY	TOPSOIL	651.35						
	210								210		SY	GRUBBING MATERIAL	651.40						
					1				1		LS	EPSC PLAN	652.10						
					50				50		HR	MONITORING EPSC PLAN	652.20						
					1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30			(N.A.B.I.) = NOT A BID ITEM			
					10				10		EACH	HAYBALES	653.15						
					30				30		SY	TEMPORARY EROSION MATTING	653.20						
					960				960		SY	PERMANENT EROSION MATTING	653.21						
					20				20		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25						
					50				50		CY	VEHICLE TRACKING PAD	653.35						
					1060				1060		LF	PROJECT DEMARCATION FENCE	653.55						
14									14		SF	TRAFFIC SIGNS, TYPE A	675.20						
												BEGIN OPTIONS							
28									28		LF	FLANGED CHANNEL SIGN POST	675.301						
28									28		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341						
												END OPTIONS							
4									4		EA	REMOVING SIGNS	675.50						
1									1		LS	SPECIAL PROVISION (TEMPORARY ROADWAY) PHASE II)	900.645						
1									1		LS	SPECIAL PROVISION (TEMPORARY ROADWAY) PHASE III)	900.645						
1									1		LU	SPECIAL PROVISION (EMISSION CONTROL DEVICE, BULLDOZER) (N.A.B.I.)	900.650						
1									1		LU	SPECIAL PROVISION (EMISSION CONTROL DEVICE, DUMP TRUCK) (N.A.B.I.)	900.650						
1									1		LU	SPECIAL PROVISION (EMISSION CONTROL DEVICE, EXCAVATOR) (N.A.B.I.)	900.650						

PROJECT NAME: **SPRINGFIELD**
PROJECT NUMBER: **ST CULV (5)**
FILE NAME: \Structures\104c178qty.xls
PROJECT MANAGER: R. R. WHITCOMB
DESIGNED BY: D. PETERSON
QUANTITY SHEET #2
PLOT DATE: 5/22/2007
DRAWN BY: D. PETERSON
CHECKED BY: W. LAMMER
SHEET 6 OF 52