QUANTITY SHEET # 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

				FULL C.E.	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						560	560	CY	COMMON EXCAVATION	203.15	5
						155	155	CY	SAND BORROW	203.31	3.7
						535	535	SY	FINE GRADING - SUBGRADE	203.40	4.2
						70	70	CY	TRENCH EXCAVATION OF EARTH	204.20	2.7
						10	10	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	
						150	150	SY	COLD PLANING - BIT. PAVEMENT	210.10	0.5
						275	275	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	3.9
						0.2	0.2	CWT	EMULSIFIED ASPHALT	404.65	0.05
						260	260	TON	BITUMINOUS CONCRETE PAVEMENT (PG ~~58~~ 64-34)	406.25	5.3
						~~2~~	~~2~~	~~CY~~	~~CONCRETE, CLASS B~~	~~501.25~~	~~0.1~~
						~~160~~	~~160~~	~~LB~~	~~REINFORCING STEEL~~	~~507.15~~	~~2~~
						87	87	LF	18" RCP CLASS IV	601.0816	
						~~1~~	~~1~~	~~EA~~	~~CAST IRON GRATE WITH FRAME, TYPE A~~	~~604.45~~	
						3	3	MGAL	DUST CONTROL WITH WATER	609.10	0.1
					4		4	CY	STONE FILL, TYPE I (MOD. - CHECK DAM)	613.10	
					34		34	CY	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10	0.7
					1		1	CY	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	613.10	0.9
						6	6	EA	YIELDING MARKER POSTS	619.17	
						133	133	LF	REMOVAL OF EXISTING FENCE	620.55	
						90	90	LF	SNOW FENCE (MOD. - ARCH)	620.70	4.2
						455	455	LF	SNOW FENCE (MOD. - PDF)	620.70	1.6
						64	64	LF	SLEEVES FOR UTILITIES (1 X 2")	625.10	
						51	51	LF	SLEEVES FOR UTILTIES (1 X 6")	625.10	0.5
						~~61~~	~~61~~	~~LF~~	~~SEAMLESS COPPER WATER TUBE (1")~~	~~629.23~~	~~0.5~~
						50	50	HR	UNIFORMED TRAFFIC OFFICERS	630.10	4
						155	155	HR	FLAGGERS	630.15	2
				1			1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
				1			1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
						1	1	LS	TRAFFIC CONTROL	641.10	
						375	375	LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40	4.2
						900	900	LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41	14
						26	26	LF	DURABLE 24" STOP BAR (THERMOPLASTIC)	646.46	0.7
						4	4	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	
						370	370	LF	TEMPORARY 4" YELLOW LINE (PAINT)	646.61	4
						45	45	EA	LINE STRIPING TARGETS	646.76	
					45		45	SY	GEOTEXTILE FOR SILT FENCE	649.51	1.2
					13		13	LB	SEED	651.15	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: FRANKLIN
PROJECT NUMBER: HES 0313(4)

FILE NAME: TOTSUMO1.DGN
PROJECT LEADER: GAMBLE
DESIGNED BY: BRC
QUANTITIES SHEET #1

PLOT DATE: 02-NOV-2006
DRAWN BY: MJF
CHECKED BY: DMB
SHEET 4 OF 26