STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
4+39.6, RT #1	NORTH SOUTH	2	24	12			2				2			13.8 14.3			~~13.8~~ 16 ~~14.3~~ 16	2														X	RELOCATE SIGNS TO POSTS		
	VERMONT 120 VERMONT 236	2	30	24			2																										RELOCATE SIGNS TO POSTS		
	→	1	21	15			1																										RELOCATE SIGNS TO POSTS		
	←																																REMOVE SIGN		
	↖	1	21	15	2.19																												M6-2L / MOUNT TO NEW POST		E-136B
21+78.3, LT #2	↑	1	21	15																													REMOVE SIGN		
	→	1	21	15	2.19				1																								M6-3 / MOUNT TO EXISTING POST		E-136B
7+22.4, LT #3	↑	1	21	15																													REMOVE SIGN		
	→	1	21	15																													REMOVE SIGN		
	←	1	21	15	2.19				1																								M6-3 / MOUNT TO EXISTING POST		E-136B
	↗	1	21	15	2.19				1																								M6-2R / MOUNT TO EXISTING POST		E-136B
20+82.3, LT #4	STOP	1	30	30			X																												
21+00.6, RT #5	STOP	1	30	30																													REMOVE SIGN		
20+20.3, LT #6	STOP MM	1 1	30 6	30 10	0.42		1				1			14 ~~13.0~~ 14&14			13.0	1															MOUNT SIGN #4 ON NEW POST, ADD MM 0120 0607 0821		E-138
	LAKE RD	1					1																										RELOCATE SIGN TO NEW POST		
	STATE PARK RD	1					1																										RELOCATED SIGN TO NEW POST		
20+50.0, RT #7	➡	1	48	24			1				2			14&14 ~~23.0~~			23.0	1															RELOCATE SIGN TO NEW POSTS		
23+34.8, LT #8	THROUGH WAY BEGINS HERE	1																															REMOVE SIGN		
	THROUGH WAY ENDS HERE	1																															REMOVE SIGN		
5+65.0, LT #9	➡	1	48	24			1				2			14&14 ~~23.0~~			23.0	1															RELOCATE SIGN TO NEW POSTS		
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 9.18	SF	EA. ~~11~~ 10	SF				FT 102 ~~87.1~~ TO BOOK #1 PAGE 101			FT 87.1					LB			EA.	LB				EA.	EA.	LB				

TO BOOK #1 PAGE 97 — TO BOOK #1 PAGE 109

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: FRANKLIN
PROJECT NUMBER: HES 0313(4)

FILE NAME: SGNSUMOI.DGN
PROJECT LEADER: GAMBLE
DESIGNED BY: BRC
TRAFFIC SIGN SUMMARY SHEET

PLOT DATE: 11-OCT-2006
DRAWN BY: MJF
CHECKED BY: DMB
SHEET 24 OF 26