



CONSTRUCTION APPROACH SIGNING

- SIGN LEGEND**
- RWA = ROAD WORK AHEAD
 - RW500 = ROAD WORK 500 FEET
 - ERW = END ROAD WORK
 - RWN = ROAD WORK NEXT 2 MILES
 - ◁ = PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

NH 2716(i) RUTLAND CITY				
HIGHWAY NAME	RWA	ERW	RW500	OTHER
U.S. ROUTE 7 - BEGIN PROJECT	2	1	2	1- PCMS
PARK STREET	1	1		
STRONGS AVENUE	1	1		
CLOVER STREET	1	1		
HOPKINS STREET	1	1		
JACKSON AVENUE	1	1		
ROYCE STREET	1	1		
ENGREM AVENUE	1			
MADISON STREET	1	1		
KILLINGTON AVENUE		1		
MAIN STREET	1	1		
SPELLMAN TERRACE		1		
EAST WASHINGTON STREET	1	1		
WASHINGTON STREET	2	2		
EAST CENTER STREET	1			
CENTER STREET	1	1		
MANSFIELD PLACE				
U.S. ROUTE 7 - STOP PROJECT	2	1	2	1- PCMS
U.S. ROUTE 4 - RESUME PROJECT				
EAST STREET	1	1		
BELLEVUE AVENUE	1	1		
HARRINGTON AVENUE		1		
LAFAYETTE STREET	1	1		
DEER STREET	1	1		
TREMONT STREET	1	1		
CROWN STREET	1	1		
PORTER STREET	1	1		
ROSS STREET	1	1		
JASMIN LANE				
TEMPLE STREET	1	1		
ST JOHN STREET				
HILLSIDE ROAD	1	1		
STRATTON ROAD	1	1		
GLEASON ROAD	1	1		
U.S. ROUTE 4 - END PROJECT	2	1	2	1- PCMS
TOTAL	32	30	6	3 - PCMS

NOTES:

1. SEE VTRANS STD. E-100 FOR ADDITIONAL SIGN PLACEMENT DETAILS.
2. TEMPORARY TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH SECTION 6 OF THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
3. CONSTRUCTION SIGNS SHALL BE IN NEW OR LIKE NEW CONDITION PER VTRANS STANDARDS.
4. DIAMOND SHAPED SIGNS SHALL BE 4' X 4' WITH BLACK LEGEND ON FLUORESCENT ORANGE BACKGROUND.
5. PORTABLE CHANGEABLE MESSAGE SIGNS ARE TO BE USED AS DIRECTED BY THE ENGINEER AND IN COMPLIANCE WITH THE MUTCD.
6. PAYMENT FOR ALL CONSTRUCTION, FLAGGER AND LANE CLOSURE SIGNING AND CONES WILL BE MADE UNDER ITEM 641.0 TRAFFIC CONTROL.
7. CONES SHALL BE USED FOR DELINEATING THE TRAVEL SPACE ALONG THE TANGENT FOR THE ENTIRE LENGTH OF ANY LANE CLOSURE.
8. FLAGGER STATIONS SHALL BE A MAXIMUM OF 500 FEET FROM THE FLAGGER AHEAD SIGN. WHEN FLAGGER STATIONS ARE MOVED BEYOND THIS DISTANCE, THE FLAGGER AHEAD SIGN SHALL BE MOVED ACCORDINGLY.
9. FLAGGER AHEAD SIGNS SHALL BE TURNED OR REMOVED WHEN FLAGGING OPERATIONS CEASE FOR MORE THAN 15 MINUTES.
10. THE CONTRACTOR SHALL MAINTAIN PEDESTRIAN THROUGH MOVEMENTS FROM ONE END OF THE CONSTRUCTION AREA TO THE OTHER, ON AT LEAST ONE SIDE OF THE STREET DURING CONSTRUCTION. ANY SIDEWALK CLOSURES SHALL MEET THE REQUIREMENTS OF THE MUTCD, PART 6.
11. PEDESTRIAN ACCESS SHALL BE PROVIDED TO ALL ADJACENT PROPERTIES, BUILDINGS, RESIDENCES AND COMMERCIAL PROPERTIES AT ALL TIMES. THIS MAY INCLUDE TEMPORARY WALKWAYS SPANNING THE CONSTRUCTION AREA.
12. IF SIDEWALKS ARE CLOSED, A TEMPORARY PEDESTRIAN ACCESS ROUTE (TPAR) SHALL BE PROVIDED ON THE SAME SIDE OF THE ROAD AS THE CLOSED SIDEWALK, IF POSSIBLE. SIGNS AND BARRICADES SHALL BE USED TO PROVIDE ADVANCED NOTICE OF THE CLOSURE AND THE ROUTE OF ANY PEDESTRIAN DETOURS. THE TPAR SHALL HAVE A MINIMUM UNOBSTRUCTED WIDTH OF 4 FEET. IF THE TPAR IS LESS THAN 5 FEET, A 5 FOOT BY 5 FOOT PASSING SPACE SHOULD BE PROVIDED AT LEAST EVERY 200 FEET. THE SURFACE OF THE TPAR SHALL BE SMOOTH AND CONTINUOUS FOR THE LENGTH OF THE TPAR. THE TPAR SHALL MAINTAIN THE SAME LEVEL OF ACCESSIBILITY AND DETECTABILITY AS THE FACILITY THAT IS BEING CLOSED. THE TPAR SHALL NOT LEAD PEDESTRIANS INTO CONFLICTS WITH VEHICLES, EQUIPMENT, OR CONSTRUCTION OPERATIONS.
13. IF THE TPAR IS ADJACENT TO MOVING TRAFFIC, CONSTRUCTION OPERATIONS/EQUIPMENT, OR DROP-OFFS, THEN CRASH WORTHY CHANNELIZING DEVICES THAT MEET THE REQUIREMENTS OF THE MUTCD SHALL BE USED.
14. THE CONTRACTOR SHALL NOT STORE OR PLACE ANY CONSTRUCTION MATERIALS, EQUIPMENT OR SIGNS IN THE PEDESTRIAN PATH OF TRAVEL.
15. THE CONTRACTOR'S OPERATIONS SHALL NOT OCCUPY SIDEWALKS EXCEPT WHERE PROPER PROTECTION AND A TPAR HAVE BEEN PROVIDED.
16. THE CONTRACTOR SHALL PROVIDE A TEMPORARY PEDESTRIAN TRAFFIC CONTROL PLAN FOR REVIEW AND WRITTEN APPROVAL A MINIMUM OF THREE WEEKS BEFORE SUCH PLAN IS IMPLEMENTED. THIS PLAN SHALL DETAIL THE CONSTRUCTION PHASING AND SCHEDULE AND THE SPECIFIC METHODS OF MAINTAINING SAFE PEDESTRIAN ACCESS THROUGHOUT THE CONSTRUCTION AREA. THIS PLAN SHALL PROVIDE THE LOCATION AND DETAILS OF TEMPORARY CONSTRUCTION SIGNING, MARKINGS, BARRICADES, CHANNELIZING DEVICES, TPARS AND METHODS TO MAINTAIN ACCESS TO ADJACENT PROPERTIES, BUSINESSES, RESIDENCES, ETC. PAYMENT FOR PROVIDING AND IMPLEMENTING THE TEMPORARY PEDESTRIAN TRAFFIC CONTROL PLAN WILL BE INCLUDED IN THE UNIT PRICE BID FOR CONTRACT ITEM 641.0.

STP 2728(i) RUTLAND CITY - PROCTOR					
HIGHWAY NAME	RWA	ERW	RW500	RWN	OTHER
U.S. BR 4 - BEGIN PROJECT	2	1	2	1	1-PCMS
RIPLEY ROAD (TH-10)	1	1			
SHEDD PLACE	1	1			
CRAMTON AVENUE	1	1			
WATKINS AVENUE	1	1			
WEST STREET	1	1			
EVERGREEN AVENUE	1	1			
STATE STREET	1	1			
PIERPOINT AVENUE	1	1			
LALOR AVENUE	1	1			
WATER STREET	1	1			
CLEVELAND AVENUE (NORTH)	1	1			
CLEVELAND AVENUE (SOUTH)	1	1			
BAXTER STREET (NORTH)	1	1			
BAXTER STREET (SOUTH)	1	1			
PINE STREET (NORTH)	1	1			
PINE STREET (SOUTH)	1	1			
SUMMER STREET	1	1			
GROVE STREET	1	1			
JUSTICE SQUARE	1				
WEST STREET (WEST)	1	1			
MERCHANTS ROW	1	1			
COTTAGE STREET		1			
CHURCH STREET	1	1			
WALES STREET	1				
ELM STREET	1	1			
COURT STREET	1	1			
LINCOLN AVENUE	1	1			
NICHOLS STREET	1	1			
COURT SQUARE	1	1			
TERRILL STREET		1			
TOTAL	30	29	2	1	1-PCMS

NOT TO SCALE

COMPOSITE TRAFFIC CONTROL PLAN SHEET	PROJECT NAME: RUTLAND CITY - PROCTOR & RUTLAND CITY
	PROJECT NUMBER: STP 2728(i), NH 2716(i) & STP 019-3(57)
	FILE NAME: p07d188.dgn
	PLOT DATE: 7/19/2013
	PROJECT LEADER: D.E.G.
	DRAWN BY: W.G.P.
	DESIGNED BY: M.J.M.
	CHECKED BY: D.E.G.
	IPARM FILE: 07d188comp+cp01.i
	SHEET 15 OF 392

FILE NAME: I:\17763\CAD\00\WST\NH_2716\07d188.comp.scp_01.dgn
 DATE/TIME: 7/19/2013 4:49:16
 USER: