STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
RUTLAND CITY U.S. BR4: 0+00.0, LT	Rutland Town / Rutland City	1	72	10	5.00						2				7.25 X 7.50			4 X 4																SIGN ID CODE VD-024		14	
	9990 1120 0100 / 9998 1119 0000	1 1	6 6	10 10	0.42 0.42																												SIGN ID CODE VD-700 SIGN ID CODE VD-700			E-138 E-138
5+00.0, RT	SPEED LIMIT 30	1	24	30	5.00						1				9.25 X			4 X																SIGN ID CODE R2-1	X		
	9990 1119 0009	1	6	10	0.42																												SIGN ID CODE VD-700			E-138
5+80.0, RT		1	30	30	6.25		1				1				(10) X 9.75			(4) X 4		SIGN WAS RELOCATED NEW POST WAS USED, OLD POST STILL PAID														SIGN ID CODE W11-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND	X		
8+81.0, RT	West St / Ripley Rd / STOP 9990 1119 0016	1 1	42 36	12 12	3.50 3.00						1				X 9.50			X 4																DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		119 119	
		1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700	X		E-138
8+90.0, LT	LEFT LANE MUST TURN LEFT	1	30	30	6.25						1				X 9.25			X 4																SIGN ID CODE R3-7L	X		
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF ~~84~~	LF	EA		LB	LB	LB		LB	LB	LB	LB									
	TOTALS				SF 36.93	SF	EA. 1	SF				LF			LF ~~84~~ 90.50					LB			EA.	LB				EA.	EA.	LB							

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT NAME: RUTLAND CITY - PROCTOR
PROJECT NUMBER: STP 2728(1)

FILE NAME: p07d282.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: L.M.B.
IPARM FILE: p07d282tss01.i
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: J.P.S.
SHEET 80 OF 392

FILE NAME = U:\1776\CADD\MISTN\STP 2728\p07d282_tss_01.dgn
DATE/TIME = 7/19/2013
USER = 4416