STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) lb/ft FOUND-ATION	3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
RUTLAND CITY U.S. BR4: 31+00.0, LT	WEST	1	24	12	2.00						1					X 10.75		X 4															SIGN ID CODE M3-4	X		
	BUSINESS	1	24	12	2.00																												SIGN ID CODE M4-3	X		
	4	1	24	24	4.00																												SIGN ID CODE MI-4	X		
31+62.0, LT	West St / Watkins Ave / YIELD / 9990 1119 0060	1 1	42 36	12 12	3.50 3.00						1					X 9.25		X 4															DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		119 119	
		1 1	36 6	36 10	3.90 0.42																												BACK-TO-BACK SIGN ID CODE RI-2 SIGN ID CODE VD-700	X		E-138
31+90.0, RT	RIGHT TURN SIGNAL	1	30	36	7.50						1					X 9.50		X 4															SIGN ID CODE RIO-IOR	X		
32+90.0, RT	NO TURN ON RED	1	30	36	7.50						1					X 9.50		X 4															SIGN ID CODE RIO-IIa	X		
33+35.0, RT	RAIL CROSSING ROAD	1	~~48~~	~~9~~	~~6.00~~				1																								SIGN ID CODE RI5-1 PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST	X		
	2 TRACKS	1	~~27~~	~~18~~	~~2.25~~																												SIGN ID CODE RI5-2P PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST	X		
	REPORT EMERGENCY TO 1-888-205-2738 CROSSING 0401-0541 ON WEST STREET	1	~~30~~	~~18~~	~~3.75~~																												SIGN ID CODE I-13A PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST		120	
												LF	LF	LF	LF	LF ~~56~~	LF		EA	LB	LB	LB		LB	LB	LB	LB								
		TOTALS			SF ~~45.82~~ 33.82	SF	EA.	SF				LF			LF ~~56~~ 55					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

SIGNS INSTALLED BY OTHERS PRIOR TO CONSTRUCTION

TRAFFIC SIGN SUMMARY SHEET #5

PROJECT NAME: RUTLAND CITY - PROCTOR
PROJECT NUMBER: STP 2728(I)

FILE NAME: p07d282.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: L.M.B.
IPARM FILE: p07d282tss05.I

PLOT DATE: 13-AUG-2013
DRAWN BY: W.G.P.
CHECKED BY: J.P.S.
SHEET 84 OF 392