STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
RUTLAND CITY U.S. BR4: 34+40.0, RT	West St / Columbian Ave / Columbian Ave	1 1 1	36 66 66	12 12 12	3.00 5.50 5.50						2					8.00 X 8.50		4 X 4															DOUBLE SIDED SIGN, SIGN ID CODE D3-1 BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		119 119 119	
																																TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
34+45.0, LT	LEFT LANE MUST TURN LEFT	1	30	30	6.25						1					X 9.00		X 4															SIGN ID CODE R3-7L	X		
34+50.0, RT	EAST	1	24	12	2.00						2					12.00 X 12.50		4 X 4															SIGN ID CODE M3-2	X		
	BUSINESS	1	24	12	2.00																												SIGN ID CODE M4-3	X		
	4	1	24	24	4.00																												SIGN ID CODE MI-4	X		
		1	21	15	2.19																												SIGN ID CODE M6-3	X		
39+12.0, LT	YIELD 9990 1119 0074	1 1	36 6	36 10	3.90 0.42						1					X 9.00		X 4															BACK-TO-BACK SIGN ID CODE RI-2 SIGN ID CODE VD-700	X		E-138
39+68.0, LT	Evergreen Ave / Evergreen Ave / Columbian Ave / Columbian Ave	1 1	60 60	12 12	5.00 5.00						3					7.00 X 8.00 8.25		4 X 4 4															BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		119 119	
		1 1	66 66	12 12	5.50 5.50																												BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		119 119	
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF ~~126~~	LF		EA	LB	LB	LB		LB	LB	LB	LB									
	TOTALS				SF 55.76	SF	EA.	SF				LF			LF ~~126~~ 118.25					LB			EA.	LB				EA.	EA.	LB						

TRAFFIC SIGN SUMMARY SHEET #6

PROJECT NAME: RUTLAND CITY - PROCTOR
PROJECT NUMBER: STP 2728(I)

FILE NAME: p07d282.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: L.M.B.
IPARM FILE: p07d282tss06.I

PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: J.P.S.
SHEET 85 OF 392

FILE NAME = U:\1776\CADD\MSTN\STP 2728\p07d282_tss_06.dgn
DATE/TIME = 7/19/2013
USER = 4416