STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
RUTLAND CITY U.S. BR4: 94+55.0, LT	9990 1119 0179	1	6	10	0.42				1																								SIGN ID CODE VD-700 PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST			E-138
95+53.0, LT	R	1	24	24	4.00						1					X 8.50		X 4															SIGN ID CODE R8-3	X		
95+68.0, RT	NO PARKING THIS SIDE	1	18	24	3.00						1					X 8.50		X 4																	120	
95+87.0, LT	NO PARKING THIS SIDE	1	18	24	3.00						1					X 8.50		X 4																	120	
95+91.0, LT	EXIT ONLY DO NOT ENTER; IMMACULATE HEART OF MARY CATHOLIC CHURCH WEEKEND MASSES SAT - 4:00 PM SUN - 6:00 & 10:15 AM PARKING ENTRANCES ON NICHOLS ST. (ABOVE)						2				1					X 11.50		X 4															SALVAGED SIGNS TO BE MOUNTED ON NEW POST.	-	-	-
	DO NOT ENTER						1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-	-
96+42.0, LT	EXIT ONLY DO NOT ENTER; IMMACULATE HEART OF MARY CATHOLIC CHURCH WEEKEND MASSES SAT - 4:00 PM SUN - 6:00 & 10:15 AM PARKING ENTRANCES ON NICHOLS ST. (ABOVE)						2				1					X 11.50		X 4															SALVAGED SIGNS TO BE MOUNTED ON NEW POST.	-	-	-
	DO NOT ENTER						1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-	-
												LF	LF	LF	LF	LF ~~70~~	LF		EA	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF 10.42	SF	EA. 6	SF				LF			LF ~~70~~ 68.50					LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #16

PROJECT NAME: RUTLAND CITY - PROCTOR
PROJECT NUMBER: STP 2728(1)

FILE NAME: p07d282.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: L.M.B.
IPARM FILE: p07d282tss16.1

PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: J.P.S.
SHEET 95 OF 392

FILE NAME = U:\17762\CADD\MSTN\STP 2728\p07d282_tss_16.dgn
DATE/TIME = 7/19/2013
USER = 4916