STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 21

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMAINED	REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
RUTLAND CITY WEST STREET: W 0+75.0, RT	RAIL ROAD CROSSING	~~1~~	~~48~~	~~9~~	~~6.00~~																												SIGN ID CODE R15-1 PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST	X		
	2 TRACKS	~~1~~	~~27~~	~~18~~	~~2.25~~																												SIGN ID CODE R15-2P PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST	X		
	REPORT EMERGENCY TO 1-877-560-6338 CROSSING #605-014L W. WEST STREET	~~1~~	~~30~~	~~18~~	~~3.75~~																												SIGN ID CODE I-13A PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST		120	
												SIGNS INSTALLED BY OTHERS PRIOR TO CONSTRUCTION																												
W 1+49.0, LT	RAIL ROAD CROSSING	~~1~~	~~48~~	~~9~~	~~6.00~~																												SIGN ID CODE R15-1 PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST	X		
	2 TRACKS	~~1~~	~~27~~	~~18~~	~~2.25~~																												SIGN ID CODE R15-2P PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST	X		
	REPORT EMERGENCY TO 1-877-560-6338 CROSSING #605-014L W. WEST STREET	~~1~~	~~30~~	~~18~~	~~3.75~~																												SIGN ID CODE I-13A PROPOSED SIGN TO BE MOUNTED ON PROPOSED SIGNAL MAST		120	
W 1+70.0, LT	STOP HERE ON RED	1	24	36	6.00						1				X 12.00		X 4																SIGN ID CODE R10-6	X		
	NO TURN ON RED	1	24	30	5.00																												SIGN ID CODE R10-11	X		
W 3+74.0, RT	STOP	1	30	30	6.25						1				X 9.75		X 4																SIGN ID CODE R1-1	X		
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	~~28~~ LF	LF		EA	LB	LB	LB		LB	LB	LB	LB										
	TOTALS				SF ~~41.25~~ 17.25	SF	EA.	SF				LF			LF		~~28~~ 29.75			LB			EA.	LB				EA.	EA.	LB							

TRAFFIC SIGN SUMMARY SHEET #21

PROJECT NAME: RUTLAND CITY - PROCTOR
PROJECT NUMBER: STP 2728(I)

FILE NAME: p07d282.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: L.M.B.
IPARM FILE: p07d282tss21.i

PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: J.P.S.
SHEET 100 OF 392

FILE NAME = U:\1776\CADD\MSTN\STP 2728\p07d282_tss_21.dgn
DATE/TIME = 7/19/2013
USER = 4416