STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 28

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMAINED	REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
PROCTOR ~~VT. ROUTE 3, 138+25.0, RT~~	~~STOP~~	~~1~~	~~30~~	~~30~~	~~6.25~~				~~1~~			DOUBLE ENTRY SEE SHEET 106 TSS SHEET 27																					~~SIGN ID CODE RI-1 PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST~~	~~X~~		
138+72.0, RT	Ormsbee Ave / East St 0038 1118 0262	1 1	42 24	8 8	2.33 1.33						1					X 10.75		X																DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		121 121	
		1	6	10	0.42																													SIGN ID CODE VD-700			E-138
138+73.0, RT		1	30	30	6.25						1					X 10.75		X 4																SIGN ID CODE WII-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND	X		
		1	24	12	2.00																													SIGN ID CODE WI6-7P SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND	X		
138+85.0, LT	STOP	1	30	30	6.25				1																									SIGN ID CODE RI-1 PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST	X		
140+01.0, RT		1	30	30	6.25						1					X 9.75		X 4																SIGN ID CODE WI-3R	X		
142+05.0, LT		1	30	30	6.25						1					X 10.25		X 4																SIGN ID CODE W3-1	X		
146+15 LT	NO PARKING										1					8.25		4																			
												LF	LF	LF	LF	~~56~~ LF	LF		EA	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF ~~37.33~~ 31.08	SF	EA.	SF				LF			LF ~~56~~ 65.75					LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #28

PROJECT NAME: RUTLAND CITY - PROCTOR
PROJECT NUMBER: STP 2728(I)

FILE NAME: p07d282.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: L.M.B.
IPARM FILE: p07d282tss28.I

PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: J.P.S.
SHEET 107 OF 392

FILE NAME = U:\1776\CADD\MISTN\STP 2728\p07d282_tss_28.dgn
DATE/TIME = 7/19/2013
USER = 4416