STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 31

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 2.0 2.5 lb/ft 1.88 2.42 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 4.0 4.0 MOD lb/ft 1.3 1.7 1.7	TUBULAR STEEL Ø (In) FOUND-ATION 3.0 3.5 4.0 5.0 lb/ft 7.6 9.0 10.8 14.6	W-SHAPE STEEL FTG. SIZE 24" 30" WEIGHT POST SIZE	SIGN REMOVED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
PROCTOR VT. ROUTE 3: 156+85.0, LT	Patch St / East St 0630 1118 0297	1	30	8	1.67						1				X		X									DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		121 121	
		1	24	8	1.33										10.75											
		1	6	10	0.42																					SIGN ID CODE VD-700			E-138
158+58.0, RT	Curtis St / East St 0630 1118 0306	1	30	8	1.67						1				X		X									DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		121 121	
		1	24	8	1.33										10.75											
		1	6	10	0.42																					SIGN ID CODE VD-700			E-138
158+75.0, LT	SPEED LIMIT 25	1	24	30	5.00						1				X		X									SIGN ID CODE R2-1	X		
															9.00		4											
160+75.0, RT	SPEED LIMIT 25	1	24	30	5.00						1				X		X									SIGN ID CODE R2-1	X		
															9.00		4											
161+75.0, RT		1	30	30	6.25						1				X		X									SIGN ID CODE W11-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND	X		
															9.75		4											
162+18.0, LT	Field St / East St 0630 1118 0305	1	24	8	1.33						1				X		X									DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		121 121	
		1	24	8	1.33										7.00		4											
		1	6	10	0.42																					SIGN ID CODE VD-700			E-138
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF ~~84~~	LF	EA	LB	LB	LB	EA	LB	LB	LB	LB					
	TOTALS				SF 26.17	SF	EA.	SF				LF			LF ~~84~~ 72.25				LB			EA.	LB				EA.	EA.	LB		

TRAFFIC SIGN SUMMARY SHEET #31

PROJECT NAME: RUTLAND CITY - PROCTOR
PROJECT NUMBER: STP 2728(I)

FILE NAME: p07d282.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: L.M.B.
IPARM FILE: p07d282tss31.i

PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: J.P.S.
SHEET 110 OF 392

FILE NAME = U:\1776\CADD\MISTN\STP 2728\p07d282_tss_31.dgn
DATE/TIME = 7/19/2013
USER = 4416