STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 32

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 2.0 2.5 lb/ft 1.88 2.42 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 4.0 4.0 MOD lb/ft 1.3 1.7 1.7	TUBULAR STEEL Ø (In) FOUND-ATION 3.0 3.5 4.0 5.0 lb/ft 7.6 9.0 10.8 14.6	W-SHAPE STEEL FTG. SIZE 24" 30" WEIGHT POST SIZE	REQUIRED FOR SIGN CAMPER	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
PROCTOR VT. ROUTE 3: 162+78.0, RT	Williams St / East St 0630 1118 0308	1 1	36 24	8 8	2.00 1.33						1					X 7.00		X 4										DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		121 121	
		1	6	10	0.42																					SIGN ID CODE VD-700			E-138
163+70.0, RT		1	30	30	6.25						1					X 10.00		X 4										SIGN ID CODE WI-2L	X		
167+87.0, LT	Garden St / East St 0630 1118 0318	1 1	30 24	8 8	1.67 1.33						1					X 10.75		X										DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		121 121	
		1	6	10	0.42																					SIGN ID CODE VD-700			E-138
169+00.0, LT		1	30	30	6.25						1					X 11.00		X 4										SIGN ID CODE WI-2R	X		
171+00.0, LT		1	30	30	6.25						1					X 10.50		X 4										SIGN ID CODE WII-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND	X		
172+60.0, LT	Newton St / East St 0630 1118 0327	1 1	36 24	8 8	2.00 1.33						1					X 10.75		X										DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		121 121	
		1	6	10	0.42																					SIGN ID CODE VD-700			E-138
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF ~~84~~	LF	EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB
	TOTALS				SF 29.67	SF	EA.	SF				LF			LF ~~84~~ 76.00				LB			EA.	LB						

TRAFFIC SIGN SUMMARY SHEET #32

PROJECT NAME: RUTLAND CITY - PROCTOR
PROJECT NUMBER: STP 2728(I)

FILE NAME: p07d282.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: L.M.B.
IPARM FILE: p07d282tss32.I

PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: J.P.S.
SHEET III OF 392

FILE NAME = U:\1776\CADD\MISTN\STP 2728\p07d282_tss_32.dgn
DATE/TIME = 7/19/2013
USER = 4416