



**PROPOSED PLAN VIEW
AARDOT 851-294L
MP 55.26
HIGHWAY CROSSING**

NOTES:

1. SEE SHEET 138 FOR CONCRETE PANEL CROSSING DETAILS.
2. SEE SHEET 132 FOR PROPOSED SCHEMATIC OF THE CONCRETE GRADE CROSSING.
3. THE CONTRACTOR SHALL DAYLIGHT THE PROPOSED 8 INCH UNDERDRAIN CARRIER PIPE TO THE ADJACENT DITCH AS DIRECTED BY THE ENGINEER.
4. SEE SHEET 133 PROPOSED GRADE CROSSING SIGNAL SHEET FOR LOCATION OF THE PROPOSED CONDUIT.
5. SEE SHEET 133 PROPOSED GRADE CROSSING SIGNAL SHEET FOR LOCATION OF THE PROPOSED SIGNAL MAST.
6. THE CONTRACTOR SHALL BE AWARE THAT AN UNDERGROUND FIBER OPTIC CABLE EXISTS AT THE WEST STREET GRADE CROSSING AT A DEPTH OF 4'-0" FROM THE EXISTING SURFACE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE AND PROTECT THIS CABLE THROUGHOUT CONSTRUCTION.
7. THE CONTRACTOR SHALL BE AWARE THAT THREE UNDERGROUND PIPES EXIST AT THE WEST STREET GRADE CROSSING. ACCORDING TO THE INFORMATION PROVIDED BY RUTLAND CITY, TWO 15 INCH SANITARY SEWER LINES AND AN 8 INCH C.I. WATER PIPE ARE LOCATED BELOW THE EXISTING SURFACE AT AN UNKNOWN DEPTH. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE AND PROTECT THESE PIPES THROUGHOUT CONSTRUCTION.
8. NO ADDITIONAL RIGHT OF WAY HAS BEEN PURCHASED FOR CONSTRUCTION OF THIS CROSSING.

AREA OF CONCRETE PANELS
(SEE NOTE 1)

NOT TO SCALE

AARDOT 851-294L PROPOSED HIGHWAY CROSSING SHEET	PROJECT NAME: RUTLAND CITY - PROCTOR
	PROJECT NUMBER: STP 2728(1)
	FILE NAME: p07d282.dgn
	PLOT DATE: 31-JUL-2013
DESIGNED BY: M.J.M.	DRAWN BY: W.G.P.
CHECKED BY: D.W.E.	
IPARM FILE: p07d282rrd03.1	SHEET 131 OF 392