

QUANTITY SHEET 1

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS			
NON-PART-ICIPATING	RAILROAD-BID ITEMS	TRAINING	FULL C.E. ITEMS	ROADWAY		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND
				160		160		CY	COMMON EXCAVATION	203.15	7.5
	600					600		CY	UNCLASSIFIED EXCAVATION	203.17	20.0
	85					85		CY	TRENCH EXCAVATION OF EARTH	204.20	5.2
				1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	
	2750			70,000		72,750		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	367.0
				180		180		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	7.9
	30					30		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	6.9
				1		1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	
	800			7900		8700		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	216.0
				1		1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	
	5					5		GAL	WATER REPELLENT, SILANE	514.10	EST.
				10		10		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	
				44		44		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	
				5		5		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	
				5		5		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	
				30		30		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	
	400					400		LF	8 INCH UNDERDRAIN PIPE	605.11	
	220					220		LF	8 INCH UNDERDRAIN CARRIER PIPE	605.21	
				50		50		HR	POWER GRADER RENTAL	608.15	EST.
				50		50		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
				30		30		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
				50		50		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
				50		50		HR	TRUCK RENTAL	608.37	EST.
				50		50		HR	LOADER RENTAL, TYPE I	608.40	EST.
				780		780		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	10.0

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
59,066	SY	MAINLINE
10,595	SY	SIDERoadS
2722	SY	RAIL CROSSING
367	SY	ROUNDING
72,750	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
1642	TON	LEVELING (TYPE IVS)
4924	TON	WEARING (TYPE IVS)
294	TON	SIDERoadS - LEVELING (TYPE IVS)
883	TON	SIDERoadS - WEARING (TYPE IVS)
380	TON	RAIL CROSSING LEVELING (TYPE IVS)
324	TON	RAIL CROSSING WEARING (TYPE IVS)
37	TON	RAIL CROSSING BASE (TYPE IIS)
216	TON	ROUNDING
8700	TON	TOTAL

QUANTITY SHEET #1	PROJECT NAME: RUTLAND CITY
	PROJECT NUMBER: NH 2716(I)
	FILE NAME: p07d188.dgn
	PLOT DATE: 31-JUL-2013
DESIGNED BY: M.J.M.	DRAWN BY: W.G.P.
CHECKED BY: D.E.G.	
IPARM FILE: 07d188qud01.I	SHEET 148 OF 392