STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 7: 32+34.0, LT		1	36	36	9.00						2					9.00 X 9.00		4 X 4															SIGN ID CODE W4-2R	X		
32+78.0, RT	EAST NORTH	1 1	24 24	12 12	2.00 2.00						2					9.75 X 9.75		4 X 4															X	SIGN ID CODE M3-2 SIGN ID CODE M3-1	X X		
	4 7	1 1	24 24	24 24	4.00 4.00																												SIGN ID CODE MI-4 SIGN ID CODE MI-4	X X		
37+40.0, LT	s Main St / Clover St	1 1	42 42	12 12	3.50 3.50						1					X 6.75		X 4																DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		239 239	
37+52.0, LT	STOP 0070 1119 0071	1 1	30 6	30 10	6.25 0.42						1					X 9.00		X 4																BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		E-138
41+17.0, RT	R	1	24	24	4.00						1					X 8.50		X 4																SIGN ID CODE R8-3	X		
41+50.0, LT	s Main St / Hopkins St	1 1	42 42	12 12	3.50 3.50						1					X 6.75		X 4																DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		239 239	
41+67.0, LT	STOP 0070 1119 0079	1 1	30 6	30 10	6.25 0.42						1					X 9.00		X 4																BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		E-138
												LF	LF	LF	LF	LF ~~126~~	LF	EA.	LB	LB	LB		LB	LB	LB	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TOTALS	SF	SF	EA.	SF	LF	LF	LB	EA.	LB	EA.	EA.	LB
	52.34					~~126~~ 113.50						

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tss02.i
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 197 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_tss_02.dgn
DATE/TIME = 7/19/2013
USER = 4916