STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 7: 43+28.0, LT	R	1	24	24	4.00						1					X 8.00		X 4															SIGN ID CODE R8-3	X		
43+60.0, RT	KEEP LEFT RIGHT	1	12	18	1.50						1					X 8.25		X 4															SIGN ID CODE R9-7	X		
43+89.0, LT	END	1	30	12	2.50						1					X 10.75		X 4															SIGN ID CODE R3-9dP	X		
	CENTER LANE ONLY	1	24	36	6.00																											SIGN ID CODE R3-9B	X		
43+95.0, RT	KEEP LEFT RIGHT	1	12	18	1.50						1					X 8.25		X 4															SIGN ID CODE R9-7	X		
43+96.0, RT	STOP 0070 1119 0083	1 1	30 6	30 10	6.25 0.42						1					X 9.00		X 4															BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		E-138
44+01.0, RT	S Main St / Jackson Ave	1 1	42 42	12 12	3.50 3.50						1					X 6.75		X 4															DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		239 239	
45+25.0, LT	S Main St / Royce St	1 1	42 36	12 12	3.50 3.00						1					X 6.75		X 4															DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		239 239	
												LF	LF	LF	LF	LF ~~98~~	LF	EA.	LB	LB	LB		LB	LB	LB	LB									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."		TOTALS	SF 35.67	SF	EA.	SF			LF			LF ~~98~~ 85.75							LB			EA.	LB				EA.	EA.	LB						

TRAFFIC SIGN SUMMARY SHEET #3	PROJECT NAME: RUTLAND CITY PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn PROJECT LEADER: D.E.G. DESIGNED BY: M.J.M. IPARM FILE: 07d188tss03.i	PLOT DATE: 7/19/2013 DRAWN BY: W.G.P. CHECKED BY: D.E.G. SHEET 198 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_tss_03.dgn
DATE/TIME = 7/19/2013
USER = 4916