STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	RECLAIMED SIGNS	REMARKS (SHS = FHWA STANDARD HIGHWAY SIGNS BOOK)	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 7: 47+85.0, RT	ONE WAY ONE WAY	1 1	36 36	12 12	3.00 3.00						1					X 10.25		X 4															BACK-TO-BACK SIGN ID CODE R6-1L SIGN ID CODE R6-1R	X X		
	STOP 0070 1119 0090	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700	X		E-138
47+95.0, RT	S Main St / Engrem Ave	1 1	42 42	12 12	3.50 3.50						1					X 6.50		X 4															DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		239 239	
48+10.0, RT	SCHOOL SPEED LIMIT 25 WHEN FLASHING	1	24	48	8.00						~~1~~					~~X~~		~~X~~		SIGNS INSTALLED ON EXISTING POST PER R.E.													SIGN ID CODE S5-1 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND	X		
48+59.0, LT		1	24	24	4.00						2					12.00 X 12.00		4 X 4															SIGN ID CODE R5-6	X		
	ON TRAVELED LANES	1	24	18	3.00																														240	
		1	24	24	4.00																												SIGN ID CODE R8-3	X		
49+06.0, LT	WEST SOUTH	1 1	24 24	12 12	2.00 2.00						2					9.75 X 9.75		4 X 4														X	SIGN ID CODE M3-4 SIGN ID CODE M3-3	X X		
	4 7	1 1	24 24	24 24	4.00 4.00																												SIGN ID CODE M1-4 SIGN ID CODE M1-4	X X		
49+30.0, RT	KEEP LEFT/RIGHT	1	12	18	1.50						1					X 8.00		X 4															SIGN ID CODE R9-7	X		
												LF	LF	LF	LF	LF ~~112~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF 52.17	SF	EA.	SF				LF				LF ~~112~~ 96.25				LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #5

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)

FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tss05.i

PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 200 OF 392

FILE NAME = U:\17762\CADD\VSTN\NH 2716\07d188_tss_05.dgn
DATE/TIME = 7/19/2013
USER = 4916