STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 7

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) lb/ft 1.75 1.88 | 2.0 2.42 | 2.5 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3 | 4.0 1.7 | 4.0 MOD 1.7 | TUBULAR STEEL Ø (in) FOUNDATION | lb/ft 3.0 7.6 | 3.5 9.0 | 4.0 10.8 | 5.0 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGNS REQUIRED | REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK | SIGN DETAIL DETAIL IN SHS | DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| U.S. ROUTE 7: 50+83.0, RT | KEEP LEFT RIGHT | 1 | 12 | 18 | 1.50 | | | | | | 1 | | | | | X 8.00 | | X 4 | | | | | | | | | | | | | | SIGN ID CODE R9-7 | X | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 50+92.0, LT | | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | X 9.00 | | X 4 | | | | | | | | | | | | | | SIGN ID CODE VR-923R | | | E-145A |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 51+35.0, RT | KEEP LEFT RIGHT | 1 | 12 | 18 | 1.50 | | | | | | 1 | | | | | X 8.00 | | X 4 | | | | | | | | | | | | | | SIGN ID CODE R9-7 | X | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 52+16.0, RT | | 1 | 24 | 24 | 4.00 | | | | | | 1 | | | | | X 8.50 | | X 4 | | | | | | | | | | | | | | SIGN ID CODE R3-2 | X | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 52+35.0, LT | ONLY | 1 | 48 | 30 | 10.00 | | | | | | 2 | | | | | 9.00 X 9.00 | | 4 X 4 | | | | | | | | | | | | | | SIGN ID CODE VR-935L | | | E-145B |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 52+36.0, RT | EAST NORTH | 1<br>1 | 24<br>24 | 12<br>12 | 2.00<br>2.00 | | | | | | 2 | | | | | 9.75 X 9.75 | | 4 X 4 | | | | | | | | | | | | | X | SIGN ID CODE M3-2<br>SIGN ID CODE M3-1 | X<br>X | | |
| | 4 7 | 1<br>1 | 24<br>24 | 24<br>24 | 4.00<br>4.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE MI-4<br>SIGN ID CODE MI-3 | X<br>X | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 52+70.0, LT | S Main St Main St | 1<br>1 | 42<br>36 | 12<br>12 | 3.50<br>3.00 | | | | | | 1 | | | | | X 6.75 | | X 4 | | | | | | | | | | | | | | DOUBLE SIDED SIGN, SIGN ID CODE D3-1<br>DOUBLE SIDED SIGN, SIGN ID CODE D3-1<br>TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. | | 239<br>240 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 53+47.0, RT | R | 1 | 24 | 24 | 4.00 | | | | | | 1 | | | | | X 8.50 | | X 4 | | | | | | | | | | | | | | SIGN ID CODE R8-3 | X | | |
| | | | | | | | | | | | | LF | LF | LF | LF | LF ~~140~~ | LF | | EA. | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | | |
| **TOTALS** | | | | | SF 45.75 | SF | EA. | SF | | | | LF | | | LF | ~~140~~ 126.25 | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

**TRAFFIC SIGN SUMMARY SHEET #7**

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tss07.i
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 202 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_tss_07.dgn
DATE/TIME = 7/19/2013
USER = 4916