STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																				REMARKS	SIGN DETAIL		
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			TUBULAR STEEL Ø (in) lb/ft					W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN REQUIRED	SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5			3.0	4.0	4.0 MOD	FOUND-ATION	3.0	3.5	4.0	5.0	24"	30"						
												1.12	2.0	3.0	1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
U.S. ROUTE 7: 54+68.0, RT	SPEED LIMIT 35	1	24	30	5.00						1					X 9.00		X 4														SIGN ID CODE R2-1	X		
54+80.0, RT	KEEP LEFT/RIGHT	1	12	18	1.50						1					X 8.00		X 4														SIGN ID CODE R9-7	X		
55+15.0, RT	KEEP LEFT/RIGHT	1	12	18	1.50						1					X 8.00		X 4														SIGN ID CODE R9-7	X		
55+16.0, RT	ONE WAY / ONE WAY	1 1	36 36	12 12	3.00 3.00						1					X 10.00		X 4														BACK-TO-BACK SIGN ID CODE R6-1L SIGN ID CODE R6-1R	X X		
	STOP 0070 1119 0104	1 1	30 6	30 10	6.25 0.42																										BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700	X		E-138
55+22.0, RT	S Main St / Spellman Ter	1 1	42 42	12 12	3.50 3.50						1					X 6.75		X 4														DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		239 239	
55+56.0, RT	R	1	24	24	4.00						1					X 8.50		X 4														SIGN ID CODE R8-3	X		
56+55.0, RT	ONLY	1	48	30	10.00						2					9.00 X 9.75		4 X 4														SIGN ID CODE VR-934L			E-145B
58+00.0, RT	USE PED SIGNAL / KEEP LEFT/RIGHT	1 1	12 12	18 18	1.50 1.50						1					X 8.00		X 4														BACK-TO-BACK SIGN ID CODE R9-5 SIGN ID CODE R9-7	X X		
												LF	LF	LF	LF	LF ~~126~~	LF	EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 44.67	SF	EA.	SF				LF			LF ~~126~~ 113.00					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #8

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tss08.i
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 203 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_tss_88.dgn
DATE/TIME = 7/19/2013
USER = 4916