STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15 (ALT A)

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 4: 7+12.0, LT		1	24	24	4.00						2				9.33 X 11.33			4 X 4															SIGN ID CODE R5-6	X		
	ON TRAVELED LANES	1	24	18	3.00																														240	
		~~1~~	~~24~~	~~24~~	~~4.00~~		1													SIGN ORIGINALLY INSTALLED AS ALT B, SALVAGED IN SWITCH TO ALT A														SIGN ID CODE R8-3	X		
8+01.0, RT	East St Woodstock Ave Woodstock Ave	1 1 1	36 60 60	12 12 12	3.00 5.00 5.00						2				8.00 X 7.75			4 X 4															BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1 SIGN ID CODE D3-1 SIGN ID CODE D3-1		240 240 240	
																																TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
8+45.0, RT	STOP 0040 1119 0016	1 1	30 6	30 10	6.25 0.42						1				X 9.00			X 4															BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700	X		E-138
9+50.0, LT	ONLY	1	48	30	10.00					2	~~2~~				~~X~~			~~X~~		POST SALVAGED FROM ALT B, INSTALLATION IN SAME SPOT														SIGN ID CODE VR-935L			E-145B
10+50.0, LT		~~1~~	~~24~~	~~24~~	~~4.00~~		1			1	~~1~~				~~X~~			~~X~~		SIGN AND POST ORIGINALLY INSTALLED AS ALT B (STA. 9+15 LT), SALVAGED IN SWITCH TO ALT A														SIGN ID CODE R8-3	X		
10+84.0, LT	Bellevue Ave Woodstock Ave Woodstock Ave	1 1 1	42 60 60	12 12 12	3.50 5.00 5.00						2				8.00 X 7.50			4 X 4															BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1 SIGN ID CODE D3-1 SIGN ID CODE D3-1		240 240 240	
																																TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
10+93.0, LT	STOP 0040 1119 0021	1 1	30 6	30 10	6.25 0.42						1				X 9.00			X 4															BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700	X		E-138

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

												LF	LF	LF	LF	LF ~~154~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS		SF ~~64.84~~ 56.84	SF	EA. 2	SF							LF			LF			~~154~~ 101.91		LB			EA.	LB				EA.	EA.	LB						

TRAFFIC SIGN SUMMARY SHEET #15 ALTERNATE A

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tssl5.1
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 210 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_sss15.dgn
DATE/TIME = 7/19/2013
USER = 4916