STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 17 (ALT A)

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REFLECTORIZED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 4: I4+94.0, RT	ONE WAY ONE WAY	1	36	12	3.00						1					X		X														BACK-TO-BACK SIGN ID CODE R6-1R SIGN ID CODE R6-1L	X X		
		1	36	12	3.00											7.50		4																	
I5+39.0, LT	R	~~1~~	~~24~~	~~24~~	~~4.00~~		1			1	~~1~~					~~X~~		~~X~~					SIGN SALVAGED IN SWITCH FROM ALT B TO ALT A											SIGN ID CODE R8-3	X		
SALVAGED TO 15+20 RT ~~I5+50.0, RT~~ AFTER INSTALLATION AT 15+50RT	STOP HERE ON RED	1	24	36	6.00		1			1	~~2~~ 1					X		X																	SIGN ID CODE R10-6	X		
	BUS STOP						2									11.00		4																	SALVAGED SIGN TO BE MOUNTED ON NEW POST. INSTALLED AS SALV. @15+50 THEN AS SALV @15+20			
~~I6+I6.0, RT~~ 15+50.0 RT	Lafayette St / Woodstock Ave / Woodstock Ave	1	42	12	3.50						2					7.75		4																	BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1		240	
		1	60	12	5.00											X		X																	SIGN ID CODE D3-1		240	
	0040 1119 0030	1	60	12	5.00											8.00		4																	SIGN ID CODE D3-1		240	
		1	6	10	0.42																													SIGN ID CODE VD-700			E-138
																																		TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
I6+48.0, LT	JCT	1	21	15	2.19						~~2~~ 1					X		X																	SIGN ID CODE M2-1	X		
	7	1	24	24	4.00											11.50		4																	SIGN ID CODE MI-4	X		
	1600 FEET	1	24	18	3.00																															240	
I6+66.0, LT	Deer St / Woodstock Ave / Woodstock Ave	1	36	12	3.00						2					8.00		4																	BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1		241	
		1	60	12	5.00											X		X																	SIGN ID CODE D3-1		240	
	0040 1119 0033	1	60	12	5.00											7.50		4																	SIGN ID CODE D3-1		240	
		1	6	10	0.42																													SIGN ID CODE VD-700			E-138
																																		TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
												LF	LF	LF	LF	LF ~~140~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."		TOTALS			SF ~~52.53~~ 48.53	SF	EA. ~~1~~ 4	SF				LF				LF ~~140~~ 89.25					LB			EA.		LB			EA.	EA.	LB						

TRAFFIC SIGN SUMMARY SHEET #17 ALTERNATE A

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tssi7.1
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 212 OF 392

FILE NAME = U:\1762\CADD\MISTN\NH 2716\07d188_tss_17.dgn
DATE/TIME = 7/19/2013
USER = 4916