STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 18 (ALT A)

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 4: 17+15.0, LT	STOP HERE ON RED	1	24	36	6.00						1					X 9.50		X 4															SIGN ID CODE R10-6	X		
18+01.0, LT	STOP HERE ON RED	1	24	36	6.00						1					X 9.50		X 4															SIGN ID CODE R10-6	X		
22+74.0, LT	R	~~1~~	~~24~~	~~24~~	~~4.00~~		1			1	~~1~~					~~X~~		~~X~~															SIGN SALVAGED IN SWITCH FROM ALT B TO ALT A SIGN ID CODE R8-3	X		
23+49.0, LT	Tremont St / Woodstock Ave / Woodstock Ave	1 1 1	42 60 60	12 12 12	3.50 5.00 5.00						2					8.00 X 7.50		4 X 4															BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1 SIGN ID CODE D3-1 SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		241 240 240	
23+64.0, LT	0040 1119 0045	1 1	36 6	36 10	3.90 0.42						1					X 9.00		X 4															BACK-TO-BACK SIGN ID CODE R1-2 SIGN ID CODE VD-700	X		E-138
25+72.0, RT	0040 1119 0048	1 1	36 6	36 10	3.90 0.42						1					X 9.00		X 4															BACK-TO-BACK SIGN ID CODE R1-2 SIGN ID CODE VD-700	X		E-138
25+73.0, RT	Crown St / Woodstock Ave / Woodstock Ave	1 1 1	42 60 60	12 12 12	3.50 5.00 5.00						2					8.00 X 7.50		4 X 4															BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1 SIGN ID CODE D3-1 SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		241 240 240	
												LF	LF	LF	LF	LF ~~126~~	LF	EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF ~~51.64~~ 47.64	SF	EA. 1	SF				LF			LF ~~126~~ 100.00				LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #18 ALTERNATE A

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tssl8.1
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 213 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_sss_18.dgn
DATE/TIME = 7/19/2013
USER = 4916