STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 20 (ALT A)

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 4: 35+85.0, LT		1	24	24	4.00						2				11.75 X 11.75			4 X 4															SIGN ID CODE R5-6	X		
	ON TRAVELED LANES	1	24	18	3.00																														240	
		~~1~~	~~24~~	~~24~~	~~4.00~~		1																SIGN SALVAGED IN SWITCH FROM ALT B TO ALT A											SIGN ID CODE R8-3	X		
36+27.0, RT	NO OUTLET	1	30	30	6.25						1				X 9.75			X 4															SIGN ID CODE W14-2	X		
36+54.0, RT	VD 0040 1119 0069	1 1	36 6	36 10	3.90 0.42						1				X 9.00			X 4															BACK-TO-BACK SIGN ID CODE RI-2 SIGN ID CODE VD-700	X		E-138
36+59.0, RT	Jasmin Ln Woodstock Ave / Woodstock Ave	1 1 1	42 60 60	12 12 12	3.50 5.00 5.00						2				8.00 X 7.75			4 X 4															BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1 SIGN ID CODE D3-1 SIGN ID CODE D3-1		241 240 240	
																																TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
37+46.0, LT	Temple St Woodstock Ave / Woodstock Ave	1 1 1	42 60 60	12 12 12	3.50 5.00 5.00						2				7.75 X 8.00			4 X 4															BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1 SIGN ID CODE D3-1 SIGN ID CODE D3-1		241 240 240	
																																TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
37+54.0, LT	STOP 0040 1119 0072	1 1	30 6	30 10	6.25 0.42						1				X 9.00			X 4															BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		E-138
												LF	LF	LF	LF	LF ~~126~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF ~~55.24~~ 51.24	SF	EA. 1	SF				LF			LF ~~126~~ 118.75					LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #20 ALTERNATE A

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tss20.1
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 215 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_tss_20.dgn
DATE/TIME = 7/19/2013
USER = 4916