STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 23 (ALT A)

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 4: 50+59.0, RT	Stratton Rd / Woodstock Ave	1	42	12	3.50						2					7.75		4														BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1		241	
		1	60	12	5.00											X		X														SIGN ID CODE D3-1		240	
		1	60	12	5.00											7.75		4														SIGN ID CODE D3-1		240	
	Stratton Rd / Woodstock Ave																																TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
51+05.0, LT	H	1	24	24	4.00						1					X 9.00		X 4														SIGN ID CODE D9-2	X		
	←	1	24	6	1.00																															E-132
51+79.0, RT	EAST	1	24	12	2.00						1					X 9.00		X 4														SIGN ID CODE M3-2	X		
	4	1	24	24	4.00																												SIGN ID CODE MI-4	X		
53+00.0, LT	END / CENTER LANE ONLY	~~1~~	~~30~~	~~12~~	~~2.50~~		1			1	+					~~X~~		~~X~~														SALVAGED IN SWITCH FROM ALT B TO ALT A			
		~~1~~	~~24~~	~~36~~	~~6.00~~		1																									SALVAGED IN SWITCH FROM ALT B TO ALT A			
53+00.0, RT	BEGIN / CENTER LANE ONLY	~~1~~	~~30~~	~~12~~	~~2.50~~		1			1	+					~~X~~		~~X~~														SALVAGED IN SWITCH FROM ALT B TO ALT A			
		~~1~~	~~24~~	~~36~~	~~6.00~~		1																									SALVAGED IN SWITCH FROM ALT B TO ALT A			
55+00.0, RT	SPEED LIMIT 35	1	24	30	5.00						1					X 9.00		X 4														SIGN ID CODE R2-1	X		
												LF	LF	LF	LF	LF ~~98~~	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF ~~46.50~~ 29.50	SF	EA. 4	SF				LF			LF ~~98~~ 62.50					LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #23 ALTERNATE A

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tss23.1
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 218 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_tss_23.dgn
DATE/TIME = 7/19/2013
USER = 4916