STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 26 (ALT A)

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
	SHEET 196 SUBTOTAL				50.00		-								-	~~56~~	60.00						-	-											
	SHEET 197 SUBTOTAL				52.34		-								-	~~126~~	113.50						-	-											
	SHEET 198 SUBTOTAL				35.67		-								-	~~98~~	85.75						-	-											
	SHEET 199 SUBTOTAL				41.92		-								-	~~112~~	103.75						-	-											
	SHEET 200 SUBTOTAL				52.17		-								-	~~112~~	96.25						-	-											
	SHEET 201 SUBTOTAL				37.25		-								-	~~112~~	104.00						-	-											
	SHEET 202 SUBTOTAL				45.75		-								-	~~140~~	126.25						-	-											
	SHEET 203 SUBTOTAL				44.67		-								-	~~126~~	113.00						-	-											
	SHEET 204 SUBTOTAL				62.25		- 2								-	~~154~~	144.50						-	-											
	SHEET 205 SUBTOTAL				54.25		-								-	~~126~~	121.00						-	-											
	SHEET 206 SUBTOTAL				~~38.86~~	32.61	2								-	~~98~~	95.50						-	-											
	SHEET 207 SUBTOTAL				41.92		-								~~14~~	~~126~~	129.25						-	-											
	SHEET 208 SUBTOTAL				~~56.24~~	55.99	-								-	~~84~~	74.75						2	~~221~~	178.60										
	SHEET 209 SUBTOTAL				9.50		-								-	~~14~~	22.75						-	-											
	SHEET 210 SUBTOTAL				~~64.84~~	56.84	- 2								-	~~154~~	101.91						-	-											
	SHEET 211 SUBTOTAL				~~73.76~~	56.76	- 5								-	~~84~~	55.50						2	~~236~~	237.50										
	SHEET 212 SUBTOTAL				~~52.53~~	48.53	+ 4								-	~~140~~	89.25						-	-											
	SHEET 213 SUBTOTAL				~~51.64~~	49.64	- 1								-	~~126~~	100.00						-	-											
	SHEET 214 SUBTOTAL				~~55.14~~	51.14	- 3								-	~~126~~	134.50						-	-											
	SHEET 215 SUBTOTAL				~~55.24~~	51.24	- 1								-	~~126~~	118.75						-	-											
	SHEET 216 SUBTOTAL				~~45.39~~	41.39	- 1								-	~~112~~	108.25						-	-											
	SHEET 217 SUBTOTAL				~~40.00~~	30.50	- 3								-	~~98~~	64.25						-	-											
	SHEET 218 SUBTOTAL				~~46.50~~	29.50	- 4								-	~~98~~	62.50						-	-											
	SHEET 219 SUBTOTAL				59.75		-								-	~~140~~	141.25						-	-											
	SHEET 220 SUBTOTAL				18.51		-								-	~~56~~	48.00						-	-											
	~~ROUNDING~~				~~0.91~~		-								~~6~~	~~16~~							-	~~43~~											
	SHEET 222				13.00											38.66																			
	FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."											LF	LF	LF	LF	LF	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
												~~20~~			~~2760~~									~~500~~											
	TOTALS				SF ~~1187~~ 1121.09	SF	EA. ~~3~~ 28	SF				LF			LF ~~2780~~ 2452.82					LB			EA. 4	LB ~~500~~ 416.10				EA.	EA.	LB						

TRAFFIC SIGN SUMMARY SHEET #26 ALTERNATE A

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2716(1)
FILE NAME: p07d188.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: 07d188tss26.1
PLOT DATE: 7/19/2013
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 221 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_tss_26.dgn
DATE/TIME = 7/19/2013
USER = 416