STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 27 (ALT A)

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
U.S. ROUTE 7: 47+98.0, RT	KEEP LEFT RIGHT	1	12	18	1.50						1					X		X														SIGN ID CODE R9-7 PROPOSED SIGN AND POST TO BE INSTALLED BY OTHERS.	X		
51+37.0, RT	S Main St / Killington Ave / Killington Ave	1 1 1	42 54 54	12 12 12	3.50 4.50 4.50						2					X		X														BACK-TO-BACK DOUBLE SIDED SIGN, SIGN ID CODE D3-1 SIGN ID CODE D3-1 SIGN ID CODE D3-1		239 239 239	
																																	TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
																																	PROPOSED SIGN AND POST TO BE INSTALLED BY OTHERS.			
52+39.0, LT	STOP 0070 1119 0106	1 1	30 6	30 10	6.25 0.42						2					X		X														BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		E-138
		1	24	24	4.00																												SIGN ID CODE R3-2 PROPOSED SIGNS AND POSTS TO BE INSTALLED BY OTHERS.	X		
67+55.0, RT	USE PED SIGNAL / KEEP LEFT RIGHT	1 1	12 12	18 18	1.50 1.50						1					X 8.00		X 4														BACK-TO-BACK SIGN ID CODE R9-5 SIGN ID CODE R9-7	X X		
																																	~~PROPOSED SIGNS AND POST~~ TO BE ~~INSTALLED BY OTHERS.~~ INSTALLED BY US			
U.S. ROUTE 4: 52+00.0, LT	ONLY	1	48	30	10.00						2					9.33 X 9.33		4 X 4														SIGN ID CODE VR-934L PROPOSED SIGN AND POSTS TO BE INSTALLED BY OTHERS.			E-145B
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF ~~112~~	LF	EA.	LB	LB	LB		LB	LB	LB	LB									
TOTALS					~~37.67~~ 13.00 SF	SF	EA.	SF				LF			LF	~~112~~ 38.66			LB			EA.	LB				EA.	EA.	LB							

NOT INSTALLED VIA CONTRACT

TRAFFIC SIGN SUMMARY SHEET #27 ALTERNATE A	PROJECT NAME: RUTLAND CITY PROJECT NUMBER: NH 2716(1)
	FILE NAME: p07d188.dgn PROJECT LEADER: D.E.G. DESIGNED BY: M.J.M. IPARM FILE: 07d188ts27.1
	PLOT DATE: 7/19/2013 DRAWN BY: W.G.P. CHECKED BY: D.E.G. SHEET 222 OF 392

FILE NAME = U:\1762\CADD\MSTN\NH 2716\07d188_tss_27.dgn
DATE/TIME = 7/19/2013
USER = 4916