



SIGN HEIGHT	NUMBER OF BOLTS
UP TO 2.5' HIGH	2
> 2.5' to 4' HIGH	3

SIGN MOUNTED TO LIGHT POLE DETAIL

NOT TO SCALE

NOTES:

1. SEE STANDARD SPECIFICATIONS & SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.
2. MOUNTING HEIGHTS WILL VARY BASED ON FIELD CONDITIONS. MOUNT SIGNS SO THAT THEY ARE VISIBLE TO MOTORIST. MINIMUM SIGN MOUNTING HEIGHT SHALL BE 7 FEET ABOVE FINISHED GROUND.
3. MOUNTING SIGNS TO LIGHT POLES SHALL BE PAID INCIDENTAL TO ALL OTHER SIGN PAY ITEMS.

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: STP 019-3(57)

FILE NAME: ...PlotFiles\rut_sgn_det.dgn PLOT DATE: 7/12/2013
PROJECT LEADER: GAE DRAWN BY: PZA
DESIGNED BY: TFD CHECKED BY: GAE
SIGN DETAILS SGD-01 SHEET 355 OF 392

