



STREET LIGHTING LEGEND	
	STREET LIGHT - 100 LED, 25' BLACK ALUMINUM POLE, 6' BRACKET ARM
	STREET LIGHT - 120 LED, 25' BLACK ALUMINUM POLE, 6' BRACKET ARM
	WIRED CONDUIT
	ELECTRICAL CONDUIT (FOR FUTURE LIGHT USE)
	JUNCTION BOX
	POWER BOARD AND CABINET/JUNCTION BOX/TC BOX/FLASHING BEACON (AS NOTED)

ONE LINE DIAGRAM

CONDUIT KEY	
(A)	3#8, 1#8G, WIRED CONDUIT (2") (PVC)
(E)	2" ELECTRICAL CONDUIT (2") (PVC)
(F)	3#2, 1#2G, WIRED CONDUIT (2") (PVC)
(H)	2#10, 1#10G, WIRED CONDUIT (1") (PVC)
(I)	3#2, 2#2G, WIRED CONDUIT (2") (PVC)
(EB)	9#2, 1#2G, WIRED CONDUIT (2") (PVC) & 2#2, 6#8, 1#10G, WIRED CONDUIT (2") (PVC)
(FA)	3#2, 1#2G, 3#8, 1#8G, WIRED CONDUIT (2") (PVC)
(GA)	5#2, 1#2G, 3#8, 1#8G, WIRED CONDUIT (2") (PVC)

REVISION	BY	DATE
CONDUIT AND LIGHTING REMOVED FROM CONTRACT	TFD	11/05/13



PROJECT NAME: RUTLAND CITY	PLOT DATE: 11/5/2013
PROJECT NUMBER: STP 019-3(57)	DRAWN BY: PZA
FILE NAME: ...rvt.lgt.det.dgn	CHECKED BY: GAE
PROJECT LEADER: GAE	SHEET 362A OF 392
DESIGNED BY: TFD	
LIGHTING DETAIL LGD-02	