

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
			ROADWAY	LANDSCAPING	EROSION CONTROL	UTILITIES	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
			1					1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			ITEM 301.35 - SUBBASE OF DENSE GRADED CRUSHED STONE
			22					22		EACH	REMOVING MEDIUM TREES	201.15	-			
			1					1		EACH	REMOVING MEDIUM STUMPS	201.20	-			7063 CY MAINLINE
			13092					13092		CY	COMMON EXCAVATION	203.15	42			194 CY ROUTE 15
			57					57		CY	SOLID ROCK EXCAVATION	203.16	4			2793 CY VT NATIONAL GUARD ROAD
			816.43					816.43		CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	2			26 CY JUGHANDLE
			1400 1500.66					1400 1500.66		CY	TRENCH EXCAVATION OF EARTH	204.20	10 15			42 CY BARNES AVE
			70					70		CY	TRENCH EXCAVATION OF ROCK	204.21	10			10118 CY SUBTOTAL
			320.66					320.66		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.			0 CY ROUNDING
			4550					4550		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	8			10118 CY TOTAL
			10118					10118		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	44			ITEM 490.30 - SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
			44.80					44.80		CWT	EMULSIFIED ASPHALT	404.65	6			2482 TON MAINLINE
			1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			149 TON MAINLINE - DRIVEWAYS
			4101.86					4101.86		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	51			537 TON ROUTE 15
											BEGIN OPTION AA					896 TON VT NATIONAL GUARD ROAD
			98					98		LF	12" RCP CLASS III	601.0805	-			38 TON JUGHANDLE
			108					108		LF	12" CPEP(SL)	601.2605	-			4102 TON SUBTOTAL
			98					98		LF	SPECIAL PROVISION ((12")(PVC)(SDR35))	900.6410	-			0 TON ROUNDING
											END OPTION AA					4102 TON TOTAL
											BEGIN OPTION AB					
			77 78					77 78		LF	15" RCP CLASS III	601.0810	-			
			77 0					77 0		LF	15" CPEP(SL)	601.2610	-			
			77 78					77 78		LF	SPECIAL PROVISION ((15")(PVC)(SDR35))	900.6411	-			
											END OPTION AB					
											BEGIN OPTION AC					
			652 589					652 589		LF	18" RCP CLASS III	601.0815	-			
			652 589					652 589		LF	18" CPEP(SL)	601.2615	-			
			652 589					652 589		LF	SPECIAL PROVISION ((18")(PVC)(SDR35))	900.6412	-			
											END OPTION AC					
			8					8		EACH	12" CPEPES	601.7005	-			
			10					10		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18	-			
			21 12					21 12		EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20	-			
			5					5		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-			
			80					80		HR	BULLDOZER RENTAL, TYPE I	608.10	EST.			
			36.50					36.50		HR	POWER GRADER RENTAL	608.15	EST.			
			110					110		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
			66					66		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
			176					176		HR	TRUCK RENTAL	608.37	EST.			
			82					82		HR	LOADER RENTAL, TYPE I	608.40	EST.			
			1.00					1.00		MGAL	DUST CONTROL WITH WATER	609.10	0.036			

RECORD DRAWING
DATE: DECEMBER 21, 2012

REVISION	BY	DATE
△ DRAINAGE REV.	JBL	04/22/11



PROJECT NAME: COLCHESTER CAMPUS CONNECTOR
PROJECT NUMBER: TCSP TCSE (007)
FILE NAME: ... \plotfiles\016-019_quant.ptf PLOT DATE: 4/20/2011
PROJECT LEADER: JBL DRAWN BY: TFD
DESIGNED BY: TFD CHECKED BY: GGC
QUANTITY SUMMARY SHEET QS-1 SHEET 16 OF 153