

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	LANDSCAPING	EROSION CONTROL	UTILITIES	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					2.0					2.0		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	0.2			
					39.66					39.66		CY	STONE FILL, TYPE I	613.10	5			
					590					590		LF	GRANITE SLOPE EDGING	616.20	4			
					320					320		LF	VERTICAL GRANITE CURB	616.21	9			
					2484					2484		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	21			
					2762					2762		LF	REMOVAL OF EXISTING CURB	616.41	4			
					1286					1286		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	8			
					28.33					28.33		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11	4			
					201.77					201.77		TON	BITUMINOUS CONCRETE SIDEWALK	618.15	1			
					268					268		SF	DETECTABLE WARNING SURFACE (CAST IRON)	618.30	-			
					2					2		EACH	BOLLARDS	619.14	-			
					4					4		EACH	YIELDING MARKER POSTS	619.17	-			
					15					15		LF	CHAIN-LINK FENCE, 6 FEET	620.12	2			
					36					36		LF	GATE FOR CHAIN-LINK FENCE, 6 FEET	620.16	-			
					4					4		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	-			
					70					70		LF	WOVEN WIRE FENCE WITH STEEL POSTS	620.25	-			
					3					3		EACH	STEEL BRACE FOR WOVEN WIRE FENCE	620.40	-			
					200					200		LF	REMOVING AND RESETTING FENCE (ORNAMENTAL)	620.50	-			
					0					0		LF	REMOVING AND RESETTING FENCE (WOOD STOCKADE)	620.50	-			
					2210					2210		LF	REMOVAL OF EXISTING FENCE	620.55	4			
					1.95					1.95		MFBM	INSULATION BOARD	622.10	-			
								27		27		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-			
								0		0		EACH	HYDRANT	629.28	-			
								1		1		EACH	RELOCATE HYDRANT	629.29	-			
								0		0		EACH	REMOVE HYDRANT	629.30	-			
					548					548		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
					2160.25					2160.25		HR	FLAGGERS	630.15	EST.			
												LS	FIELD OFFICE, ENGINEERS	631.10	-			
												LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
												LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
												DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
					1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
					600					600		LF	DURABLE 4 INCH WHITE LINE	646.400	5			
					1960					1960		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	45			
					6008					6008		LF	DURABLE 4 INCH YELLOW LINE	646.410	4			
					1290					1290		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	19			
					6290					6290		LF	DURABLE 6 INCH WHITE LINE	646.420	1			
					147					147		LF	DURABLE 8 INCH WHITE LINE	646.440	6			
					321					321		LF	DURABLE 24 INCH STOP BAR	646.480	3			
					73					73		EACH	DURABLE LETTER OR SYMBOL	646.490	-			

**RECORD DRAWING**  
**DATE: DECEMBER 21, 2012**

REVISION	BY	DATE
ADDENDUM - 1	JBL	01/24/11



PROJECT NAME: COLCHESTER CAMPUS CONNECTOR  
PROJECT NUMBER: TCSP TCSE (007)  
FILE NAME: ...\\plotfiles\016-019\_quant.prf PLOT DATE: 4/20/2011  
PROJECT LEADER: JBL DRAWN BY: TFD  
DESIGNED BY: TFD CHECKED BY: GGG  
**QUANTITY SUMMARY SHEET QS-2** SHEET 17 OF 153