

# QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	LANDSCAPING	EROSION CONTROL	UTILITIES	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								13		13		EACH	JUNCTION BOX	678.26	-			
								<del>570</del>		<del>570</del>		LF	ELECTRICAL CONDUIT SLEEVE (4")(PVC)(SCH80)	678.301	<del>7</del>			
								390		390		LF	ELECTRICAL CONDUIT SLEEVE (6")(PVC)(SCH80)	678.302	4			
								<del>180</del>		<del>180</del>		LF	ELECTRICAL CONDUIT SLEEVE (6")(PVC)(SCH80)	678.302	3			
								49		49		EACH	LIGHT POLE BASE	679.21	-			
								49		49		EACH	LIGHT POLE	679.45	-			
								49		49		EACH	LUMINAIRE	679.50	-			
								1		1		EACH	POWER DROP STANCHION, STREET LIGHTING	679.55	-			
					1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
					43					43		CY	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608	4			
								7		7		EACH	SPECIAL PROVISION ((SANITARY SEWER MANHOLE)(4' ID))	900.6201	-			
								2		2		EACH	SPECIAL PROVISION (CHANGE ELEVATION OF SEWER MANHOLE)	900.6202	-			
								14		14		EACH	SPECIAL PROVISION (CLEAN EXISTING DRAINAGE STRUCTURE)	900.6203	-			
								2		2		EACH	SPECIAL PROVISION (DRYWELL)	900.6204	-			
								33		33		EACH	SPECIAL PROVISION (INLET PROTECTION DEVICE, FILTER FIBER)	900.6205	-			
					2					2		EACH	SPECIAL PROVISION (REMOVE AND RESET BLOCK WALL)	900.6206	-			
					1					1		EACH	SPECIAL PROVISION (REMOVE AND RESET BUILDING)	900.6207	-			
								5		5		EACH	SPECIAL PROVISION (SEWER CLEANOUT)	900.6208	-			
					2					2		EACH	SPECIAL PROVISION (SLIDE GATE)	900.6209	-			
								196.5		196.5		LF	SPECIAL PROVISION ((PVC SEWER PIPE)(4"))	900.6401	-			
								366		366		LF	SPECIAL PROVISION ((PVC SEWER PIPE)(6"))	900.6402	-			
								965		965		LF	SPECIAL PROVISION ((PVC SEWER PIPE)(8"))	900.6403	-			
								24		24		LF	SPECIAL PROVISION ((SANITARY SEWER FORCE MAIN)(2" SDR 26 PVC))	900.6404	-			
								36		36		LF	SPECIAL PROVISION ((SANITARY SEWER FORCE MAIN)(4" CLASS 52 D.I.))	900.6405	-			
								<del>87</del>		<del>87</del>		LF	SPECIAL PROVISION (15" DUCTILE IRON PIPE, CEMENT LINED)	900.6406	-			
								191		191		LF	SPECIAL PROVISION (16" CL 52 DUCTILE IRON PIPE, CEMENT LINED)	900.6407	-			
								<del>342</del>		<del>342</del>		LF	SPECIAL PROVISION (18" DUCTILE IRON PIPE, CEMENT LINED)	900.6407	-			
								483		483		LF	SPECIAL PROVISION (18" CL 52 DUCTILE IRON PIPE, CEMENT LINED)	900.6408	13			
								<del>2270</del>		<del>2270</del>		LF	SPECIAL PROVISION (CHAIN LINK FENCE W/ BARBED WIRE, 8 FEET - 6 FEET)	900.6408	13			
					1600					1600		LF	SPECIAL PROVISION (SAW CUTTING SURFACES AND PAVEMENTS)	900.6409	23			
								1		1		LS	SPECIAL PROVISION (ELECTRIC DEMOLITION)	900.6451	-			
								1		1		LS	SPECIAL PROVISION (ELECTRIC POWER BOARD AND CABINET)	900.6452	-			
					1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.6453	-			
								1		1		LS	SPECIAL PROVISION (TRANSFER TO NEW SYSTEM, SANITARY SEWER)	900.6454	-			

**RECORD DRAWING**  
**DATE: DECEMBER 21, 2012**

REVISION	BY	DATE
ADDENDUM - 1	JBL	01/24 /11
DRAINAGE REV.	JBL	04/22/11
LIGHTING REV.		



PROJECT NAME:	COLCHESTER CAMPUS CONNECTOR	PLOT DATE:	4/20/2011
PROJECT NUMBER:	TCSP TCSE (007)	DRAWN BY:	TFD
DESIGNED BY:	TFD	CHECKED BY:	GGG
<b>QUANTITY SUMMARY SHEET QS-4</b>		SHEET	19 OF 153