

QUANTITY SHEET

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | | TOTALS | | | DESCRIPTIONS | | | DETAILED SUMMARY OF QUANTITIES | | | | | | | |
|---------------------------------|--|--|--|--|--|--|--|--|--|--|----------------|-----------------|--------------|--------------|-----------------|-------|--------------------------------|-------|------|---|-------------|------------|------|-------|
| | | | | | | | | | | | FULL E&C ITEMS | EROSION CONTROL | LAND-SCAPING | ROADWAY | BRIDGE QUANTITY | ROUND | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | QUANTITIES | UNIT | ITEMS |
| | | | | | | | | | | | | 20 | | | | EST | 20 | | CY | STONE FILL, TYPE I (MOD.-INLET PROTECTION) | 613.10 | | | |
| | | | | | | | | | | | | 60 | | | | EST | 60 | | CY | STONE FILL, TYPE I (MOD.-CONSTRUCTION ENTRANCE) | 613.10 | | | |
| | | | | | | | | | | | | 5250 | | | | 69 | 5250 | | CY | STONE FILL, TYPE II | 613.11 | | | |
| | | | | | | | | | | | | 2650 | | | | 69 | 2650 | | CY | STONE FILL, TYPE III | 613.12 | | | |
| | | | | | | | | | | | | | | 35 | | 2 | 35 | | TON | BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS | 616.47 | | | |
| | | | | | | | | | | | | | | 1 | | | 1 | | EACH | RELOCATE MAIL BOX, SINGLE SUPPORT | 617.10 | | | |
| | | | | | | | | | | | | | | | | 13 | 13 | | EACH | YIELDING MARKER POSTS | 619.17 | | | |
| | | | | | | | | | | | | | | | | 12 | 12 | | LF | GATE FOR CHAIN-LINK FENCE, 4 FEET (VINYL - GREEN) | 620.15 | | | |
| | | | | | | | | | | | | | | | | 900 | 900 | | LF | SNOW FENCE (MOD.-ARCH) | 620.70 | | | |
| | | | | | | | | | | | | | | | | 1800 | 1800 | | LF | SNOW FENCE (MOD.-PDF) | 620.70 | | | |
| | | | | | | | | | | | | | | | | 325 | 325 | | LF | STEEL BEAM GUARDRAIL (GALVANIZED) | 621.20 | | | |
| | | | | | | | | | | | | | | | | 1 | 1 | | EACH | ANCHOR FOR STEEL BEAM RAIL | 621.60 | | | |
| | | | | | | | | | | | | | | | | 62.5 | 62.5 | | LF | REMOVL AND DISP OF GUARDRAIL | 621.80 | | | |
| | | | | | | | | | | | | | | | | 2 | 2 | | EACH | REMOVL AND DISP OF GUIDE POSTS | 621.81 | | | |
| | | | | | | | | | | | | | | | | 500 | 500 | | LF | TEMPORARY TRAFFIC BARRIER | 621.90 | | | |
| | | | | | | | | | | | | | | | | 100 | 100 | | LF | INCLINOMETER | 623.30 | | | |
| | | | | | | | | | | | | | | | | 60 | 60 | | LF | GROUND WATER OBSERVATION WELL | 623.50 | | | |
| | | | | | | | | | | | | | | | | 20 | 20 | | LF | PIPE INSULATION (3/4" DIA.) | 629.44 | | | |
| | | | | | | | | | | | | | | | | 20 | 20 | | LF | PIPE INSULATION (2" DIA.) | 629.44 | | | |
| | | | | | | | | | | | | | | | | 300 | 300 | | HR | UNIFORMED TRAFFIC OFFICERS | 630.10 | | | |
| | | | | | | | | | | | | | | | | 600 | 600 | | HR | FLAGGERS | 630.15 | | | |
| | | | | | | | | | | | | 1 | | | | | 1 | | LS | FIELD OFFICE-ENGINEERS | 631.10 | | | |
| | | | | | | | | | | | | 1 | | | | | 1 | | LS | TESTING EQUIPMENT - CONCRETE | 631.16 | | | |
| | | | | | | | | | | | | 1 | | | | | 1 | | LS | TESTING EQUIPMENT - BITUMINOUS | 631.17 | | | |
| | | | | | | | | | | | | 1 | | | | | 1 | | LU | FIELD OFFICE - TELEPHONE (N.A.B.I.) | 631.25 | | | |
| | | | | | | | | | | | | | | | | 1 | 1 | | LS | MOBILIZATION / DEMOBILIZATION | 635.11 | | | |
| | | | | | | | | | | | | | | | | 1 | 1 | | LS | UTILITY SYSTEM (MOD.- MOVE PROPANE TANK) | 636.15 | | | |
| | | | | | | | | | | | | | | | | 1 | 1 | | LS | TRAFFIC CONTROL | 641.10 | | | |
| | | | | | | | | | | | | | | | | 3 | 3 | | EACH | PORTABLE CHANGEABLE MESSAGE SIGN | 641.15 | | | |
| | | | | | | | | | | | | | | | | 1750 | 1750 | | LF | 4" WHITE LINE | 646.20 | | | |
| | | | | | | | | | | | | | | | | 1750 | 1750 | | LF | 4" YELLOW LINE | 646.21 | | | |
| | | | | | | | | | | | | | | | | 1750 | 1750 | | LF | TEMPORARY 4" WHITE LINE (PAINT) | 646.60 | | | |
| | | | | | | | | | | | | | | | | 1750 | 1750 | | LF | TEMPORARY 4" WHITE LINE (TAPE, TYPE II) | 646.60 | | | |
| | | | | | | | | | | | | | | | | 1750 | 1750 | | LF | TEMPORARY 4" YELLOW LINE (PAINT) | 646.61 | | | |
| | | | | | | | | | | | | | | | | 1750 | 1750 | | LF | TEMPORARY 4" YELLOW LINE (TAPE, TYPE II) | 646.61 | | | |
| | | | | | | | | | | | | | | | | 50 | 50 | | EACH | LINE STRIPING TARGETS | 646.76 | | | |
| | | | | | | | | | | | | 4450 | | | | 2 | 4450 | | SY | GEOTEXTILE UNDER STONE FILL | 649.31 | | | |
| | | | | | | | | | | | | | | 3500 | | 30 | 3500 | | SY | GEOTEXTILE FOR UNDERDRAN TRENCH LINING | 649.41 | | | |
| | | | | | | | | | | | | 500 | | | | EST | 500 | | SY | GEOTEXTILE FOR SILT FENCE | 649.51 | | | |
| | | | | | | | | | | | | 250 | | | | 13 | 250 | | LB | SEED | 651.15 | | | |

PROJECT NAME: **HARDWICK**
PROJECT NUMBER: **STP ST 030-3(4)**
FILE NAME: D04e060qty.dgn PLOT DATE: 3/2/05
PROJECT MANAGER: **A. BOMBARDIER** DRAWN BY: **M. NUTTER**
DESIGNED BY: **M. NUTTER** CHECKED BY: **A. BOMBARDIER**
QUANTITY SHEET #2 SHEET 5 OF 63